


## **Historic, Archive Document**

Do not assume content reflects current scientific knowledge, policies, or practices.



# WATER RUNOFF STUDY FOR MAIN DRAINAGEWAYS AND OUTLETS



## FLORENCE COUNTY, SOUTH CAROLINA

Prepared under sponsorship of  
FLORENCE COUNTY  
FLORENCE COUNTY COUNCIL  
and  
FLORENCE SOIL AND WATER CONSERVATION DISTRICT  
in cooperation with the  
U. S. Department of Agriculture  
Soil Conservation Service

## NATIONAL

A  
G  
R  
I  
C  
U  
L  
T  
U  
R  
A  
L



LIBRARY

To find inf  
in this Wat

1. The app

2. Refer t  
on this

3. This in  
drainag

4. Turn to  
this ma

Area Number and, also, the main or lateral number such as M-1,  
L-1, L-2, etc.

5. Turn to this planning area number in the ENGINEERING AND DESIGN  
DATA Sheets and locate the Main or Lateral desired on this sheet.

Each time a lateral enters the main canal, the Main is broken into a  
section at this point. Laterals also are broken into sections at  
points where other laterals enter them. This was necessary to design  
each section to carry the flow increase. Also, it was necessary to  
break mains and laterals into sections at state and county road  
crossings in order to design the proper size culverts and bridges at  
these points.

It must be kept in mind that the information given in the "ENGINEERING  
AND DESIGN DATA" Sheets begins at the upper end of each watershed and  
proceeds, section by section, to the outlet.

EXAMPLE: To find information for the ditch crossing S. C. Highway  
51 approximately 1 mile northwest of Hyman refer to figure 3.

"Index to Atlas Sheets"; The index indicates that the point where this  
ditch crosses highway 51 can be found on Sheet 8 at the back of the  
report.

Sheet 8 designates this ditch as main number 3 (M3) in Planning Area 7  
and shows it was designed in four Segments A, B, C, and D.

A general description of Planning Area 7 is found on page 15 of the  
report and the detailed Engineering and Design Data Table is on Page  
91.

Beginning at the upstream end of the ditch, M3A, in the table for  
Area 7 on page 91 and proceeding downward toward its outlet end, it  
is found that it crosses highway 51 at the end of Segment M3B. Total  
length of the ditch is estimated to be 6900'. The various criteria for  
engineering and design estimates may be obtained from the table for  
each segment.

D DESIGN DATA" SHEETS

or Lateral Ditch contained  
eps should be taken:

olved should be known.

SHEETS" and locate the area

of the map sheet showing the

ocate the area desired on  
map will show the "Planning



## FOREWORD

About 1730 the interior of the South Carolina colony was divided into a number of townships. This was a plan designed by the colony's Governor Robert Johnson to attract Protestant settlers to this area, partly to serve as a buffer to Indian attacks. (The Pee Dee and Catawba Indian tribes inhabited the area and regions along the Pee Dee River.) Pioneers were offered free land and various other inducements to settle in these townships. The idea proved successful and brought the first permanent white settlements into what presently is the Florence Area.

Queensborough Township, including what is now the lower portion of Florence County was laid out in 1733. It initially was successful in attracting small farmers, as the land was suited to large plantations. Among these were a group of Pennsylvania Welsh farmers who asked for a land grant and in 1736 formed a community at Long Bluff (present day Society Hill). Their main crops were hemp and flax. These Welsh Baptists established churches around the area along with Methodists, Presbyterians, and Protestant Episcopalians.

The communities increased and after the Revolution, during which Francis Marion's raids were well known, the agricultural industry grew and cotton and corn remained the staple crops throughout much of the 19th century. The agricultural interior of South Carolina was linked with the seaport of Wilmington by the Wilmington-Manchester Railroad in 1849. The way station was named "Florence" in 1854 in honor of Florence Harllee, daughter of the president of the railroad. It was not until 1888 however that Florence County was established after agitation by citizens to form a new county. The new county was formed from portions of Clarendon, Darlington, Marion and Williamsburg counties with Florence becoming the county seat in 1889. <sup>1</sup>

Since the first settlement was made near the Queensborough Township in 1736, the existing problem of imperfect internal and surface drainage has affected the growth and development of this area in South Carolina.

The higher areas of land were used by the first settlers for homesteads and for small fields to produce food crops. Low, wet lands were left in their natural state. As settlements grew and more land was needed for farming operations, it was necessary to install some type of drainage system on individual farms. These drainage systems were usually excavated by hand, many with slave labor. As a result, these small ditches were inadequate and only partially met the drainage needs. The lack of knowledge of drainage systems and the availability of only hand tools retarded the design and installation of complete systems.

With the increase in land use and particularly with the advent of modern construction machinery such as the bulldozer, dragline and backhoe, it became relatively easy to excavate larger canals and outlet ditches needed for adequate drainage. Even with the new machines, much of the drainage work installed has been the result of expediency incident to population growth and did not follow a well developed plan of action. Improving the quantity and quality of agricultural crops and providing well drained areas for home sites are essential to perpetuate economic growth of a community; providing additional drainage is necessary as a first step toward enhancing the environment and increasing income for its people.

The Water Runoff Study for Main Drainageways and Outlets in Florence County is the direct result of foresight and interest of the county authorities and the Florence Soil and Water Conservation District Commissioners who saw the need for a plan to enhance the potential development of the county. Agencies at all levels of government - city, county, state, and federal - as well as private enterprise and numerous individuals, cooperated in the development of the plan. The Florence County Council appropriated funds for the local share of the cost of the study including the publication of this report. Technical assistance was furnished by the Soil Conservation Service.

The plan and information contained in this report will be of interest to organizations concerned with land use in the county. The cooperation of other agencies, groups and individuals in the use of this report is encouraged.

## CONTENTS

TEXT	Page
INTRODUCTION AND SCOPE-----	1
FACTORS AFFECTING WATER DISPOSAL-----	2
Topography-----	2
Rivers and Streams-----	2
Rainfall-----	3
Soils-----	3
Land Use and Ownership-----	3
Wildlife-----	6
Existing Drainage System-----	7
Maintenance-----	7
EXCESS WATER DISPOSAL PRINCIPLES-----	7
Surface Drainage-----	8
Subsurface Drainage-----	8
Water Runoff Systems-----	8
Excess Water Removal Requirements-----	9
DESIGN CRITERIA-----	9
Drainage Curves-----	9
Velocity-----	10
Channel Cross Section-----	12
Culverts and Bridges-----	12
Right-of-Way Requirement- Spoil Bank Management-----	12
DESCRIPTION OF AREAS-----	14
Area 1 - Florence-Mars Bluff-Quinby-----	14
Area 2 - Timmons ville-Cartersville-Sardis-Cusaac Crossroads-----	14
Area 3 - Savannah Grove-Peniel-Effingham-----	14
Area 4 - Claussen-Evergreen-Willow Creek-----	14
Area 5 - Olanta-Scranton-Lake City-Byrds Crossroads-----	15
Area 6 - Friendfield-Coward-Highhill-Camerontown-----	15
Area 7 - Hyman-Pamplico-Blossom-Salem-----	15
Area 8 - Poston-Salem-Vox-Johnsonville-----	16
FACTORS CONSIDERED IN PREPARATION OF PLAN-----	16
ENGINEERING CONSIDERATIONS-----	17
Design-----	17
Acquisition of Rights-of-Way-----	18
Maintenance of Channels-----	18
Obstructions-----	18
DEFINITION OF TERMS-----	18
TECHNICAL REFERENCES-----	20
AUTHORITY AND ACKNOWLEDGEMENT-----	21
EXPLANATION OF ENGINEERING DATA TABLES-----	23

## TEXT

	Page
ENGINEERING AND DESIGN DATA	
Area 1 - Florence-Mars Bluff-Quinby-----	25
Area 2 - Timmons ville-Cartersville-Sardis-Cusaac Crossroads-----	38
Area 3 - Savannah Grove-Peni el-Effingham-----	56
Area 4 - Claussen-Evergreen-Willow Creek-----	65
Area 5 - Olanta-Scranton-Lake City-Byrds Crossroads-----	76
Area 6 - Friendfield-Coward-Highhill-Camerontown-----	82
Area 7 - Hyman-Pamplico-Blossom-Salem-----	91
Area 8 - Poston-Salem-Vox-Johnsonville-----	99
MAPS SHOWING THE DRAINAGE PLAN	
Follows Page-----	108

## FIGURES

Figure No. 1 - Drainage Coefficient	
Curves-----	11
Figure No. 2 - Typical Main Ditch	
Cross Section Showing Basis for	
Determining Right-of-Way Width-----	13
Figure No. 3 - Index to Map Sheets-----	109

## TABLES

Table No. 1 - Total Inches of	
Precipitation-----	4
Table No. 2 - Precipitation	
Extremes-----	5
Table No. 3 - Rainfall in Inches for	
Selected Durations-----	5

WATER RUNOFF STUDY  
FOR MAIN DRAINAGEWAYS AND OUTLETS  
FLORENCE COUNTY, SOUTH CAROLINA

#### INTRODUCTION AND SCOPE

One of the most significant needs for efficient use and development of the land resources in Florence County is the provision for the management of excess rainfall runoff. The lack of adequate drainageways is extremely detrimental to existing and future land use management. Flooding results in frequent and costly damage to natural wildlife habitats, agricultural crops, and public and private property. Flooding also disrupts facilities in urban and industrial areas. In recent years the need for drainage has affected and virtually prevented housing development progress in many areas where septic tank drain fields were to be installed.

The need to reduce flooding through improvement of drainageways and outlets is a problem that demands priority attention.

The development of a water disposal plan for an entire county should logically begin with a study of the need for main drainageways and outlets to remove excess water.

The purpose of this study is to point out the extent and severity of the excess water problems and to estimate the sizes and quantities of water disposal systems to convey excess water properly to adequate outlets.

The engineering and design data in this report are based on reconnaissance surveys, information presently available, and knowledge gained by long experience in planning and establishing drainage facilities in the county. These data are adequate for the purpose of determining preliminary designs and preliminary cost estimates based on present land use, but are not adequate, however, for the preparation of final construction plans, designs and costs. The data in this report can be used by engineers as guides to determine types of additional surveys and investigations needed to secure detailed information for final design.

A discussion of some of the principal criteria used in sizing channels is included, as well as technical references which can supply information for final design.



*Panoramic view of flooded farm land and paved road as a result of heavy rainfall and a need for additional excess water removal facilities.*



## FACTORS AFFECTING WATER DISPOSAL

The location of Florence County, in the Atlantic Coastal Plain, along with the county's physical features result in complex water runoff problems. Physical features that contribute to these problems are topography, rivers and streams, rainfall, soils, and land use and ownership, all of which are inter-related. A brief discussion of how these features affect the water disposal, and a description of the existing drainage system follows.

### Topography

Topography is a severely limiting factor affecting excess water disposal. The land is generally level with slight undulations in some sections of the county, however, the removal of excess water is restricted in most sections due to inadequate drainageways. The natural drains, other than the rivers, are broad, have flat grades and are heavily vegetated. In their present state, little or no channel exists, causing extreme flooding in depressed areas although potential outlets are available.



*"Flopped" tobacco - a high value crop loss caused by lack of proper drainage in an agricultural area.*

## Rivers and Streams

Florence County is covered with a network of rivers and streams and swamp runs that have a significant effect on the drainage pattern. The Great Pee Dee River forms the entire eastern boundary of the county with a number of small tributaries flowing to it. Jefferies Creek, just south of the city of Florence, cuts through the county from West to East and empties into the Great Pee Dee River. Lynches River, forming a portion of the county's western boundary, curves up northeasterly into the center of the county and then southeasterly slicing the county in half. It joins the Great Pee Dee River in the extreme southeastern corner near Johnsonville.

In addition to these main rivers, several big swamps affect large areas of land. These include Black Creek, Middle Swamp, Lake Swamp, Sparrow Swamp, Lynches Lake, Camp Branch, Willow Creek, and Big Swamp.

All of these rivers and swamps affect the county's drainage. The main rivers are well defined; their water levels are generally at lower elevations and provide an outlet for higher ground drainage. However, these rivers and other large creeks are constantly a threat to adjacent low-lying areas. After heavy rainfall periods flood water overflow inundates these areas and blocks tributary outlets. A sizeable area of the county is affected in this manner.

This report does not include any study of the main streams. It does include a study of the tributaries to relieve adjacent lands of flooding as quickly as possible after heavy rains when river floods recede.





*Flooded cropland caused by inadequate outlet for this field ditch.*

### Rainfall

U. S. Weather Bureau records, Table No. 1, show monthly and annual totals of rainfall for Florence and vicinity. The average annual rainfall of 45 inches would not cause a serious drainage problem if it were evenly distributed. The most serious drainage problems occur in low flat areas which are flooded by high intensity, short duration rain storms.

The design of water disposal systems and supporting structures are related to the amount of runoff that can be expected from storms of differing intensities and durations. (See Tables Nos. 2 & 3)

### Soils

According to the Soil Survey for Florence County, more than 70 percent of the soils have excess water problems. This fact points out the need for management of excess water in the county. It would not be desirable or practical to provide drainage for all of the wet soils in the county; the degree of drainage needed is dependent on the type of soil and the land use.

Soils have characteristics which influence the need for and the degree of drainage. Some of the more important characteristics are slope, texture, infiltration, permeability, structure, depth, waterholding capacity and depth to water table. Fine (clayey) textured soils have slow internal water movement and will not readily respond to deep ditches. Shallow ditches to remove surface water provide the best practical means for improvement of these soils for most uses. Sandy soils, having high or fluctuating water tables, respond to subsurface drainage but present some problems in the design of stable open ditches.

A knowledge of the characteristics and the engineering properties of the soils is essential in planning, designing and constructing adequate runoff water management systems.

### Land Use and Ownership

Changes in land use in recent years have had an adverse effect on water disposal in the county. One of the most significant of these is urbanization. Areas being developed for housing, shopping centers and industry in most instances have inadequate excess water disposal systems facilities. Most of the systems now in use were established to handle the agricultural needs of the areas. They are not adequate to handle the increased runoff resulting from urbanization. Roof tops, paved roads, compaction, raised water tables resulting from septic tanks and drain field installations, and elimination of some ditches during development, have all caused an increase in the amount of excess water to be disposed of.

TABLE NO. 1  
TOTAL INCHES OF PRECIPITATION  
FLORENCE, SOUTH CAROLINA

Year	Jan.	Feb.	Mar.	Apr.	May	June	July	Aug.	Sept.	Oct.	Nov.	Dec.	Ann'l
1941	2.33	2.16	5.83	3.22	.35	8.57	8.63	6.91	1.19	1.50	.67	6.80	48.16
1942	2.56	2.55	5.25	2.57	3.89	3.11	9.25	5.57	1.59	.53	.79	3.34	41.00
1943	3.40	1.21	5.26	2.29	1.57	3.17	5.43	1.12	1.90	T	2.91	4.30	32.56
1944	2.97	3.92	4.89	2.92	3.36	3.68	13.36	2.71	2.87	3.74	1.57	.94	46.93
1945	1.76	2.55	4.15	3.17	3.31	4.23	5.75	6.39	13.43	1.40	.98	7.86	54.98
1946	1.63	2.43	2.30	3.88	3.17	3.14	5.73	4.80	1.05	3.37	1.95	.53	33.98
1947	2.40	.19	4.29	7.78	1.99	2.88	10.14	7.65	3.47	1.90	7.16	4.03	53.88
1948	3.69	5.09	6.19	2.86	5.39	6.68	1.34	4.08	4.15	3.70	8.16	4.28	55.61
1949	.87	4.56	1.33	7.84	3.62	3.91	3.89	9.24	3.54	2.27	2.29	1.58	44.94
1950	2.48	.97	3.98	3.81	2.89	3.41	8.39	4.00	2.42	3.16	.89	3.79	40.19
1951	.94	.82	4.20	3.40	.56	7.32	10.79	4.28	3.81	.55	2.49	3.02	42.18
1952	2.21	4.30	5.47	2.58	1.96	5.74	1.21	10.89	4.86	1.22	2.43	2.46	45.33
1953	2.75	4.44	3.60	2.37	1.31	4.11	3.72	4.84	5.07	.00	1.37	6.51	40.09
1954	2.39	1.31	3.31	1.75	4.35	.24	2.09	1.25	.87	7.29	.81	1.84	27.50
1955	4.05	1.66	1.22	5.13	3.23	2.47	4.84	3.15	6.63	1.30	1.87	.36	35.91
1956	1.69	5.83	2.31	2.92	2.30	4.90	3.10	4.22	4.39	2.21	1.40	2.52	37.79
1957	1.83	2.26	5.48	.53	4.19	4.93	2.55	5.68	9.03	.80	4.19	2.29	43.76
1958	4.49	3.78	4.29	5.97	1.87	7.97	4.45	2.81	.67	3.16	.44	2.28	42.18
1959	2.85	5.36	4.91	7.60	3.90	3.55	13.68	3.93	7.20	6.83	1.11	3.79	64.71
1960	4.46	5.62	3.39	1.76	1.49	6.09	11.14	1.46	4.65	3.69	1.80	2.10	47.65
1961	1.24	3.55	4.23	5.59	5.35	9.29	4.86	4.75	2.13	.34	1.57	1.43	44.33
1962	3.68	4.14	4.53	3.09	.81	4.57	3.71	2.22	3.55	.28	3.37	1.81	35.76
1963	5.05	2.27	1.77	2.20	3.14	2.86	3.83	1.52	4.13	.43	3.78	2.44	33.42
1964	5.77	5.21	3.67	3.38	1.97	4.10	10.06	5.49	8.10	8.16	.48	2.58	58.97
1965	.80	5.69	6.33	2.79	1.89	8.86	6.21	8.53	3.66	1.65	1.68	.54	48.63
1966	6.99	3.49	2.72	3.03	8.18	3.70	6.26	4.99	2.50	.33	1.00	3.34	46.53
1967	2.64	2.40	2.35	1.25	5.49	1.56	4.40	6.72	2.71	1.12	2.93	2.59	36.16
1968	3.45	.84	1.66	3.02	1.34	5.97	9.94	1.97	.57	6.61	4.56	3.03	42.96
1969	1.52	4.37	3.94	3.50	3.57	3.35	4.85	5.70	4.14	.83	2.24	2.97	40.98
1970	2.47	2.96	6.83	.65	1.71	1.73	3.25	4.55	5.29	3.03	.68	3.07	36.22
1971	4.35	2.88	10.96	3.28	3.12	4.20	7.65	5.85	1.07	7.98	1.49	1.42	54.25
1972	5.22	3.11	2.64	.60	7.12	6.19	4.42	4.99	2.29	1.01	4.29	3.25	45.13
1973	3.95	4.91	3.58	3.41	2.21	7.78	8.35	8.73	2.76	.72	.46	6.52	53.38
1974	5.04	4.11	3.39	2.87	5.63	3.21	4.31	11.46	5.46	.18	3.51	4.94	54.11
1975	5.70	5.17	3.77	4.62	4.32	1.47	7.59	3.77	5.62	2.19	1.37	5.80	51.39
1976	3.26	1.08	4.12	.59	5.03	8.17	5.56	1.50	.92	3.79	2.83	5.27	42.12
Aver- age Rain- fall	3.14	3.26	4.11	3.28	3.21	4.64	6.24	4.94	3.82	2.42	2.26	3.21	44.55

From Rainfall Data, U.S. Weather Bureau - Florence, S.C. FAA  
Airport Station.

TABLE NO. 2  
PRECIPITATION EXTREMES (1941-1976)

	Maximum Monthly	Year	Minimum Monthly	Year
January	6.99	1966	0.80	1965
February	5.83	1956	0.19	1947
March	10.96	1971	1.22	1955
April	7.84	1949	0.53	1957
May	8.18	1966	0.35	1941
June	9.29	1961	0.24	1954
July	13.68	1959	1.21	1952
August	11.46	1974	1.12	1943
September	13.43	1945	0.57	1968
October	8.16	1964	0.00	1953
November	8.16	1948	0.44	1958
December	7.86	1945	0.36	1955

Rainfall Data, U.S. Weather Bureau - Florence, S.C.  
FAA Airport Station

TABLE NO. 3  
RAINFALL IN INCHES FOR SELECTED DURATIONS  
FLORENCE COUNTY, SOUTH CAROLINA

	30 Min.	1 Hour	2 Hour	3 Hour	6 Hour	12 Hour	24 Hour
1 Year	1.3	1.7	1.9	2.1	2.4	2.9	3.3
2 Years	1.5	1.9	2.3	2.5	2.9	3.4	4.0
5 Years	1.9	2.4	2.9	3.2	3.8	4.4	5.2
10 Years	2.2	2.8	3.4	3.7	4.4	5.2	6.0
25 Years	2.5	3.2	3.8	4.2	5.0	6.0	6.8
50 Years	2.8	3.5	4.3	4.7	5.6	6.7	7.8
100 Years	3.1	3.7	4.8	5.2	6.3	7.5	8.8

From U.S. Weather Bureau, Technical Paper No. 40,  
"Rainfall Frequency Atlas of the United States."





*Damage to homes and septic tank field drains results from heavy rains and poor water disposal systems.*



*Excessive rainfall runoff backed up in the drainageway outlet inundated and prevented use of an industrial parking lot near Coward, South Carolina.*

Drainage culverts under driveways and roads in new as well as established subdivisions, are critical factors contributing to poor local drainage. Head losses alone, resulting from widespread use of under-designed culverts create local flooding conditions.

As urbanization continues, the present water disposal systems will become increasingly inadequate to handle the increased runoff, and additional flooding will occur. After urbanization has taken place, it is extremely expensive and sometimes impossible to provide adequate water disposal. Regulations may be needed to insure that adequate water disposal plans are included in these areas during development.

Land ownership often is a factor in the installation of drainage improvements. Frequently it is necessary for one owner to go on another's property, or go through it, to obtain an outlet. In larger group projects it is necessary to cross a number of land owners to reach adequate outlets. In either case, it is imperative that right-of-way easements be obtained before work can be begun.

### Wildlife

Proper drainage also plays an important part in another land use - upland wildlife management. Populations of game species such as deer, quail, turkey, and rabbits are enhanced in a safer and healthier wildlife environment provided in well drained areas. Unseasonably heavy rains can cause mass drowning of young animals and nestlings. Biting insect pests are reduced as a result of diminished breeding places in these areas where excess water is removed. Improvement of the habitat through proper water disposal allows greater natural food production. Seeded spoil banks not only control erosion but also provide food and cover, and travelways for wildlife.

Care should be taken, however, to protect certain wetland areas. Drainage of high value wetland sites is detrimental to wetland wildlife. Game species, such as wild ducks, geese, snipe, and some furbearers, depend heavily upon the water covered and water saturated areas for food and cover. Destruction of these areas through drainage could drastically reduce wetland wildlife species.

The discharge of dredged or fill material in inland waters and wetlands is regulated by the Federal

Water Pollution Control Act Amendments of 1972. Prior to placing fill material in wetlands, application for a Section 404 permit should be made to the nearest district office of the U. S. Army Corps of Engineers who are assigned the responsibility for carrying out Section 404 of the regulations.

The South Carolina Wildlife and Marine Resources Department can provide information, evaluation, and assistance in planning water management practices in wetland areas.

#### Existing Drainage System

Existing canals are usually located in natural water courses. However, in many instances, alignment is poor due to the fact that canals were located on existing property lines, cleared land borders, meandering branch runs or other physical features that were inconsistent with efficient channel flow conditions.

With the exception of some recently excavated canals, many drainage systems in rural and urban areas generally lack depth and capacity, have very flat grades and inadequate outlets. One exception to these conditions is the Lynches Lake - Camp Branch Watershed project located in the southwestern quadrant of the county between Olanta and Scranton. This project, completed in 1968, improved the natural waterway, and benefited hundreds of acres of land in this area. While the capacity of this improved waterway is still generally good, there is a need for some maintenance, especially vegetative removal, to restore full flow. A number of other smaller drainage projects completed in recent years, as well as numerous natural waterways, that serve as outlets also need the same type of maintenance to restore full flow.



*Old ditches can be brought back to full capacity and service by simple maintenance or enlarging.*

#### Maintenance

Lack of adequate maintenance is a factor affecting the capacity of drainage canals and ditches. Most of the existing drainage canals in the county were dug by hand many years ago; some were dug or enlarged by the Works Progress Administration (WPA) in the 1930's; clumsy floating dredges were used on some of the larger ones. These methods left nearly vertical side slopes with excavated material placed immediately next to the ditch. Access to practically all canals is restricted by high spoil banks which are covered by a heavy growth of trees and brush. Being continuous for long distances, these spoil banks prevent surface drainage resulting in ponding behind the banks. The extent of economic and practical maintenance by machine is limited largely due to these spoil placement practices.

#### EXCESS WATER DISPOSAL PRINCIPLES

This report presents a plan for the location and needed capacities of main drainageways based on present land use. This is, however, only a preliminary step in the establishment of a complete water disposal system. Further steps in designing the system will include the exact size, depth,



and grade of each drainageway determined only by a more detailed investigation and survey by qualified individuals. In some locations, detailed investigations might prove that existing drainageways are adequate.

Drainage systems are divided into two broad categories - surface drainage and subsurface drainage.

#### Surface Drainage

Surface drainage systems provide for removal of excess water from the land surface to an outlet. Surface water can best be moved by shallow graded channels or by forming the land surface to a uniform slope. Surface drainage facilities are particularly applicable to soils having slow permeability rates. Surface drainage on these soils is used to prevent ponding in shallow depression areas and also to divert water from protected areas to natural or excavated channels.

#### Subsurface Drainage

Subsurface drainage removes water from beneath the surface of the soil by facilities which create a difference in hydraulic head. The resulting hydraulic head causes water to move through the soil to an outlet at a lower elevation. This may be accomplished by open ditch drains or by closed drains of tile or perforated tubing. Often a combination of open and closed drains is used for subsurface drainage. Open ditch drains sometimes have an added advantage in that they can remove both surface and subsurface water. Properly installed closed drains require very little maintenance. They can also be designed to remove surface water by providing protected drop inlets or catch basins that simulate small storm sewer systems.



*A ditch with good design section and managed spoil can serve as Surface and Subsurface Water disposal outlet for several landowners.*

The purpose of subsurface drainage is to lower the water table to a point where it will not interfere with plant growth or the use of the land for residential or other purposes. The minimum depth below the surface at which water tables should be maintained depends on the purpose for which the land is to be used. Water tables, fluctuating from a lower level upward to or near the surface, may not be as great a problem for some agricultural uses as they would be in populated areas where construction of buildings, septic tanks, lawns and gardens, or streets would be damaged.

#### Water Runoff Systems

The components of an excess water disposal system are as follows:

The Collection Segment is that part of the drainage system which first picks up water from the land. It may consist of shallow trapezoidal ditches having flat side slopes, V or W type ditches, bedded areas, or graded land surfaces.

The Disposal Segment receives water from the collection segment and conveys it, usually in an open channel or floodway to an outlet.



Generally this report concerns itself with the disposal segment of the drainage system.

The Outlet is the end point of any section of a drainage system beyond which the conveyance system no longer guides or controls the water it discharges.

#### Excess Water Removal Requirements

The water disposal system should be designed so that flooding will not occur in critical parts of the watershed for a period of time sufficient to cause damage or disrupt utilities and services. For urban areas, design should provide for the removal of runoff from the design storm with a minimum of flooding. In agricultural areas, the degree of protection required by crops varies considerably, depending on their tolerance to the amount and duration of excess water. Truck crops are the most susceptible to damage from excess surface water, with damage occurring to some when flooded for the relatively short period of 24 hours or less. General crops such as corn and grain are less susceptible, with pasture being the least subject to water damage. Woodland areas are the least subject to damage from flooding for prolonged periods.

Poorly drained soils adversely affect the use of the land for most purposes. On agricultural land, high water tables restrict root depth; the soil temperature is lowered and air circulation is severely limited depending on the degree of soil saturation. Wet spots in the field delay farm operations and shorten the growing season.

In residential areas, poorly drained soils adversely affect the construction, maintenance and use of roads and streets in addition to the harmful effects on ornamental plants,

flower gardens and lawns. These soils also limit or prohibit the development of some areas, preventing the proper functioning of septic tanks or tile field drains and thus contribute to health hazards.



*Road culverts at lower elevation provide an outlet for low lying drainage areas and subsurface water - Soil cement bag-type headwall stabilized fill.*

#### DESIGN CRITERIA

The design of excess water disposal systems and supporting structures is based largely on Hydrology and Hydraulics. This report is limited to the application of these sciences as they apply to water disposal systems. Data and detailed information on the design of the drainageways are tabulated on the pages following this narrative section.

#### Drainage Curves

To determine the required runoff and design capacity for the drainageways, the Cypress Creek formula was used:

$$Q = CM^{5/6}$$

Where: Q = Average rate of runoff in cubic feet per second for which the ditch is to be designed.

C = Appropriate drainage coefficient for 1 square mile of watershed.

M = Square miles of watershed.

This formula provides an economical and effective design for open ditches if C is selected properly.

The drainage coefficient is the rate of removal of runoff to provide a specific degree of drainage protection to an area. Land use, soils, topography and rainfall intensities and duration determine the selection of drainage coefficients.

Three runoff curves have been developed from which required drainage capacities of open ditches in this report were computed. Each curve is based on a particular land use. For purposes of this report, curves selected were for present land use. (See Figure No. 1)

The highest curve used is for general crops followed in descending order by the curve for pasture or grassland and the curve for forest or woodland.

These curves provide for the removal, in 24 hours, of the following estimated amounts of runoff for a one square mile area.

General crops curve	-	1.67 inches
Pasture Curve	-	.93 inches
Woodland Curve	-	.37 inches

#### Velocity

The maximum safe velocity in an open channel is determined based on soil characteristics, the shape of the channel, and available means for the stabilization of the channel after construction. The optimum velocity for channels, based on soil conditions in Florence County, is approximately 2 feet per second. The soils are predominantly sandy loams with sandy clay subsoils. There are some areas where sands occur, therefore the design of

channels in these lighter soils must consider the need for checking erosion and bank sloughing that might occur, immediately following construction, when water tables are high.

Velocities were computed by use of Manning's formula:

$$V = \frac{1.486}{n} \times r^{2/3} \times s^{1/2}$$

Where: n = roughness coefficient  
r = hydraulic radius  
s = slope in feet per foot along the ditch


The proper design of a ditch cross section requires the selection of the proper value of "n". The following tabulations were used for selection of these values in the design of main canals with good alignment:

<u>Hydraulic Radius*</u>	<u>"n"</u>
Less than 2.5	.045
2.5 to 4.0	.040
4.0 to 5.0	.035
Over 5.0	.030

\*The hydraulic radius is obtained by dividing the proposed area of the channel cross section by its wetted perimeter.

Roughness coefficients were selected anticipating flow retardance features, vegetative growth and sedimentation, several years after construction. Newly dug channels with lower roughness coefficients will have higher velocities initially. These velocities will reduce as the vegetation and sedimentation occur, especially during the first few years.





Watershed Area In Square Miles

Figure No. 1 — Drainage Coefficient Curves



*When larger ditches cross roads, a bridge provides unrestricted flow capacity for excess water runoff.*

### Channel Cross Section

Depth and width of the channel are both significant considerations in design. Channels designed for sub-surface drainage must be deep enough to intercept at some depth below the surface and allow for safe disposal. The channel depth must be adequate for lateral ditches and tile drains. Other things considered to favor deeper channels with resulting narrower bottom widths are: less right-of-way is required, vegetative growth on the wetted perimeter is reduced, and conditions are less favorable for the formation of sand-bars. A channel approximately as deep as its bottom width - within practical and economical limits - will remain effective for a longer period because it has more favorable hydraulic characteristics.

A minimum bottom width of 3.0 feet was used in sizing main channels, for this report. This conforms to a bucket width of small dragline excavating equipment commonly available in the county. Bottom widths were selected as narrow as design and construction criteria would permit to maintain a favorable hydraulic section with higher velocity to help prevent siltation.

Side slopes of the ditch, as well as depth and allowable velocities, are determined primarily by topography, soil conditions, proposed maintenance methods, and a need for adequate rights-of-way. To satisfy these conditions, 1 to 1 side slopes were used for main channels in this report. Detailed soil surveys may indicate subsoils that would allow  $\frac{1}{2}$  to 1 side slopes in many areas. This side slope has been used satisfactorily in numerous cases in the county. In urban areas, flatter side slopes may be desirable for aesthetic and easier maintenance purposes.


In fine sands, or other unstable soils, having high water tables, sloughing of side slopes may be expected immediately after excavation. Sloughing will continue until the water table becomes established at the lower level. The problem can be controlled somewhat in wide channels by utilizing a pilot channel to lower the water table, followed by final construction when the slopes have become more stabilized. If a pilot channel is not used, a maintenance operation may be required soon after the water table has stabilized to restore the desired cross section.

### Culverts and Bridges

Culverts generally restrict the flow of water in ditches by decreasing the flow area thereby causing a loss in hydraulic head. This was considered in sizing main channels. At culverts, during design flow, the hydraulic gradient was set low enough to keep the profile of the water surface well within the channel cross section in all critical areas.

### Right-of-Way Requirement-Spoil Bank Management

Factors governing width of rights-of-way can best be understood by consulting Figure No. 2. The principal requirements for spoil bank management



TYPICAL CROSS SECTION — SPOIL SHAPED ONE SIDE


$$\text{R.O.W.} = 5 + T + 6 + S + 15$$

$$S = 1.3 A \div 3 \text{ (where } A = \text{Excavated Area)}$$

$$\text{Wooded Area - R.O.W.} = T + \frac{1.3 A}{3} + 26$$

$$\text{Open Area - R.O.W.} = T + \frac{1.3 A}{3} + 11$$

Bottom Width Less than 20 ft.



TYPICAL CROSS SECTION — SPOIL SHAPED BOTH SIDES

$$\text{R.O.W.} = 15 + S + 6 + T + 6 + S + 15$$

$$\text{R.O.W.} = 2S + T + 42$$

$$2S = 1.3 A \div 6 \text{ (where } A = \text{Excavated Area)}$$

$$\text{Wooded Area - R.O.W.} = T + \frac{1.3 A}{6} + 42$$

$$\text{Open Area - R.O.W.} = T + \frac{1.3 A}{6} + 22$$

Bottom Width More Than 20 ft.

FIGURE 2



includes a right-of-way wide enough for placement of spoil and debris and shaping of spoil into a travelway for maintenance equipment. No berm widths are needed where the spoil is to be spread and shaped to establish a travelway on top of it. A berm width of 15 feet is recommended for access and to avoid slope failure where spoil is to be stacked and not shaped.

#### DESCRIPTION OF AREAS

To facilitate planning, the county was divided into 8 areas, generally along watershed divides or large drainageways. This delineation allowed the study to be made of the present drainage system and its needs peculiar to each area. A brief description of each area and the features having some influence on the study of its drainage problems follows:

##### Area 1 - Florence - Mars Bluff - Quinby

Area 1 joins Darlington County in the northernmost part of the county and is bordered on the South by Middle Swamp and Jefferies Creek and on the East by the Great Pee Dee River. It includes the metropolitan area of Florence, the county seat with its industrial and urban areas, as well as the small town of Quinby. Interstate Highways 95 and 20 cut through the area west of the city of Florence. Farming interests in the extreme Western part of the area and the Eastern section produce crops of tobacco, corn and soybeans. A sizable amount of this area is wet land or land subject to flooding along Black Creek, Middle Swamp, Jefferies Creek and the large Pee Dee River Swamp. Some of the agricultural soils include Wagram, Norfolk and Goldsboro. Wildlife along the larger swamps include waterfowl, deer, and raccoons.

##### Area 2 - Timmons ville - Cartersville - Sardis - Cusaac Crossroads

This section of the county joins Darlington County and is bordered on the southwest by the Lynches River and extends eastward to Lake Swamp. Included in this area are the towns of Timmons ville and Cartersville, on U. S. Highway 76 that cuts across the upper portion. Interstate Highway 95 slices through the mid section and U. S. Highway 301 cuts across the lower portion. Sparrow Swamp runs through almost the entire length of Area 2 which along with the Lynches River Swamp and Lake Swamp involve large areas of wet natured or flooded soils. Farming in the better higher elevations produces good crops of tobacco, corn, and soybeans.

##### Area 3 - Savannah Grove - Peniel - Effingham

Area 3, immediately south of the city of Florence is bordered by Lake Swamp on the west and extends across U. S. Highway 52 to include a section along the Lynches River and a tributary, McCall Branch. The northern boundary is Middle Swamp and the southern boundary mainly the Lynches River.

U. S. Highways 301 and 52 cut through this area of rather flat land with several small branches that drain into the Lynches River. A number of soils with high water tables are present, however, fair crops of tobacco, corn and soybeans are produced on the higher better drained fields of Norfolk, Wagram, and Goldsboro. Some of the wet natured soils are Coxville, Lynchburg and Rains.

##### Area 4 - Claussen - Evergreen - Willow Creek

This area includes the entire drainage area of Willow Creek and its tributaries which runs through the



center. It extends from the Seaboard Coast Line Railroad on its western border to the Great Pee Dee River on the eastern border and from Jefferies Creek on the north southward to include the drainage area of Cypress Creek. The area is rather flat and contains several wet natured soils such as Lynchburg, Coxville, and Rains. The better drained soils such as Norfolk and Wagram along with drained Goldsboro and the above mentioned soils produce crops as grown in the other areas - mainly tobacco, corn and soybeans.

Area 5 - Olanta - Scranton -  
Lake City - Byrds Crossroads

In the southwestern corner of the county, this area joins Sumter, Clarendon and Williamsburg Counties on the west and south and extends over to U. S. Highway 52 on its eastern side and includes the town of Lake City and a small area east of Lake City. It extends up to the Lynches River on its northern border.

U. S. Highway 301 cuts across the western side of the area, U. S. Highway 52 across the Eastern side and U. S. Highway 378 runs along its southern edge while the rest of this area is covered with a network of state and county roads. The land is fairly level and includes a number of wet natured soils that need drainage improvements generally, such as Goldsboro, Lynchburg, Coxville, Rains, and Pantego. The Lynches Lake Swamp and Camp Branch section in the center of Area 5 was improved with a drainage channel, the Lynches Lake - Camp Branch Watershed project, completed in 1969. This project provided an outlet for drainage from dozens of farms in the area between Olanta and Scranton.

The farms in this area produce the same crops as the other areas - tobacco, corn, soybeans. In addition,

in the Lake City vicinity, several kinds of truck crops are produced such as beans, peas, tomatoes, squash, cucumbers and watermelons. This section of the county along with most of the others has wildlife that includes squirrels, deer, quail, and doves in large numbers.

Area 6 - Friendfield - Coward -  
Highhill - Camerontown

Area 6 includes the lands immediately east of Coward and Lake City on U. S. Highway 52, and eastward across the Lynches River to lands on the other side of the river drained by several small tributaries. The area extends southward to the Lynches Lake Swamp and northward to the New Hope community. With the Lynches River running north and south through the center of area 6, a large acreage is subject to flooding from it and its tributaries.

The soils are wet natured, in general, and poorly drained - they include Leaf, Coxville, Lynchburg, Rains and Cahaba.

The higher elevation field soils, in lesser acreages, include some Norfolk and Goldsboro. Crops grown in the area are somewhat limited to fair production of corn and soybeans with some tobacco and truck crops on higher field locations.

Area 7 - Hyman - Pamplico - Blossom -  
Salem

Area 7 joins area 6 on the east side and extends over to the Great Pee Dee River on the eastern side. It includes all the drainage area of Big Swamp and its small tributaries south to where it empties into the Lynches River. Big Swamp flows southward through the center of this area, influences the wetness of all low lying land adjacent to it.

The area is relatively flat with some

depression areas which need drainage improvements. The higher field areas contain soils like Wagram, Norfolk and Goldsboro while the major wooded areas have Duplin, Lynchburg and Rains soils.

This, as well as other areas of the county, is considered highly agricultural, producing good crops of tobacco, corn, soybeans and some truck.

Wildlife in this area abounds including deer, raccoon, squirrel, waterfowl in the Pee Dee Swamp, doves and quail.

#### Area 8 - Poston - Salem - Vox - Johnsonville

Area 8 is located in the extreme southeastern corner of the county and is bounded on the East by the Great Pee Dee River on the south by Muddy Creek and the Williamsburg County line and joins area 6 and area 7.

The Lynches River and Lynches Lake Swamp traverse the area from east to west and influence a major portion of the lands adjacent to them. A sand mining company has excavated sand on sizable acreages just north of the Lynches River near Johnsonville.

The soils in the area include Norfolk, Wagram, Duplin and Varina in the section north of the river and Chipley, Olanta, and Lakeland south of the river. Like the other areas the main crops grown on the better soil types are tobacco, corn and soybeans. The area is generally flat with low lying lands adjacent to the streams and swamps. Wildlife abounds in the swamps and includes deer, raccoons, squirrels and waterfowl, while on the higher areas there are also quail and doves in good numbers.

#### FACTORS CONSIDERED IN PREPARATION OF PLAN

The Water Runoff Study was prepared by engineers of the Soil Conservation Service with the assistance of the Florence County Development Board. On-site investigations were made of the outlets for each main canal, and the factors affecting water disposal within the watershed, such as land use, river stages, flooding, and the time of year in which flooding occurs, were studied.

Present land use and anticipated future land use was considered in sizing the drainage ditches for this study. Engineering information available through the Florence Field Office of the Soil Conservation Service was also used, particularly that pertaining to drainage investigations.

U. S. Geological Survey Topographic Maps were used in many areas to determine the general topography within each watershed and to assist in delineation of watersheds. A limited amount of instrument surveying was done in some areas to determine direction of runoff and outlets.

Aerial photographs, scale 1" = 1320', flown in 1969, were used in recording field data and for the preparation of the drainage plan.

Agencies and commercial concerns, having knowledge of specific drainage problems, were consulted in making decisions in certain areas. Also, maps, surveys and plans available from these agencies were used.

In most instances, mains were located along natural drains with modifications in alignment to improve the flow and collection of water. All needed laterals within the watersheds were not located since the purpose

of the study is to locate and size only the main canals which will furnish a means of disposal of runoff from all parts of the watershed. All mains terminate in rivers, creeks or natural outlets at a point where they have adequate capacity and depth.

No attempt was made to locate underground utilities, such as telephone cables, gas pipelines, water mains, and conduits, as a part of this study. However, due consideration must be given to the location of these underground utilities during the preparation of the final plans.

No designs are included for the ditches receiving runoff at the edges of the city of Florence. A Storm Drainage Study was completed for the Greater Florence Planning Area by LBC & W - Harwood Beebe Company in 1974. Reference to this publication can be made for design of these outlets.

Watersheds draining into the county from adjoining counties were included in the design of main canals. The mains, however, are shown beginning at the county line. Attention was given to possible land use changes in adjacent counties that would affect runoff coming into these watersheds.

#### ENGINEERING CONSIDERATIONS

Engineering considerations for planning, design, construction, maintenance and other items pertinent to the main drainageways and outlets feasibility study are listed below:

##### Design

This Water Runoff Study was made to estimate the extent of needed main disposal outlets and the physical practicability of drainage in the county. Detailed engineering surveys

and designs will be required before any part of the proposed plan can be constructed. All improvements should be made continuous. Layout and construction should begin at the outlet end and continue upstream.

Plans and designs contained in this report do not include a complete study of underground storm sewers near towns found in Areas 1, 2, 5, 6, 7, and 8. Sufficient engineering data was not available on the sewers in these areas to include in this report. Detailed studies will be needed to determine the adequacy of these storm sewers and any additional needs or modifications.

No attempt was made in this study to size culverts. Culverts at railroad and road crossings should be designed to satisfy the minimum requirements based on expected flow. Increases in size of these structures may be desirable to provide an added safety factor for passing runoff in excess of designed flow where future unforeseen improvements are to be made in the vicinity.

The South Carolina Wildlife and Marine Resources Department and other organizations or agencies concerned with environmental protection should be consulted when the ecology of an area may be affected by the construction of main drainage canals.

As previously mentioned under the topic of WILDLIFE, the Federal Water Pollution Control Act Amendment of 1972, Section 404, regulates the placing of fill material in coastal and inland waters and wetlands. Before undertaking any construction in water or wetland areas an application for a Section 404 permit should be made to the nearest district office of the U. S. Army Corps of Engineers.



## Acquisition of Rights-of-Way

The means for, and the acquisition of, adequate rights-of-way for the installation of main canals is absolutely essential. The right-of-way must be adequate to meet the width requirements for the channel section, berm, spoil management, and to assure access.

## Maintenance of Channels

A well-organized and adequately financed maintenance program is essential for proper maintenance of channels.

Provision for annual maintenance or periodic reconstruction to maintain the effectiveness of the channel must be considered prior to design. Many water disposal projects fail to function as designed and this can be directly attributed to an inadequate maintenance program. Maintenance of designed depth of channels is one of the most important items in a maintenance program. The cost of maintenance may be reduced considerably if provision is made in channel designs for easy access and stabilization of silt-contributing areas, such as ditch side slopes, new road fills and road ditch intersections, immediately following construction.

## Obstructions

Construction of fences, walks and other structures that may retard channel flow should not be permitted. Other structures such as culverts, bridge piers, trestles, etc., should be designed to result in minimum interference with the channel flow. Dumping trash, garbage and other debris in channels should be prohibited.

## DEFINITION OF TERMS

Brief descriptions of terms used in this report are listed below in

alphabetical order.

c.f.s. - Abbreviation for cubic feet per seconds; a unit of waterflow sometimes called "second feet."

Infiltration - The entrance of water into surface horizons of soil.

Internal Drainage - The movement of water through the soil profile. The rate is affected by the texture of the surface soil and of the subsoil and by the height of the water table. A wet, deep sand may have slow internal drainage when the water table is high, and rapid internal drainage when the water table is low. A plastic, sandy clay soil may have slow internal drainage regardless of water table height.

Lateral Ditch - A major ditch in a drainage system which serves as a link between the main ditch and the collection system in a segment of the watershed.

Main Canal (Ditch or Channel) - The principal channel which conducts the drainage water from the watershed to the outlet.

Permeability Rate - The rate of movement of water through the soil.

Profile, Soil - A vertical section of the soil through all its horizons and extending into the parent material.

Reach - A length of channel selected for use in hydraulic computations.

Relief - The elevations or inequalities of a land surface, considered collectively.

Runoff, Surface - The total rainfall minus losses from interception, infiltration, evapotranspiration, and surface storage; that which moves across the ground to a stream or depression.

Runoff, Subsurface - Water that infiltrates the soil and reappears as seepage or spring flow.

Soil Drainage - (1) The rapidity and extent of the removal of water from the soil by runoff and flow through the soil to underground spaces. (2) As a condition of the soil, the frequency and duration of periods when the soil is free of saturation. For example, in well-drained soils, the water is removed readily, but not rapidly; in poorly drained soils, the root zone is waterlogged for long periods and the roots of ordinary crop plants cannot get enough oxygen; and in excessively drained soils, the water is removed so completely that most crop plants are damaged by lack of water.

Soil Structure - The arrangement of the individual grains and aggregates that make up the soil mass; may refer to the natural arrangements of the soil when in place and undisturbed or to the soil at any degree of disturbance.

Subsoil - In soils with weak profile development, the subsoil can be defined as the soil below the plowed soil (or its equivalent of surface soil) in which roots normally grow.

Surface Soil - The soil ordinarily moved in tillage or the equivalent in uncultivated soil about six to ten inches in thickness.

Terrace (Geological) - An old alluvial plain, ordinarily flat or undulating, bordering a river, lake or the sea. Stream terraces are frequently called second bottoms, as contrasted to flood plains, and are seldom subject to overflow. Marine terraces were deposited by the sea and are generally wide.

Texture, Soil - The relative proportions of sand, silt and clay particles in a mass of soil. The

basic textural classes, in order of increasing proportions of fine particles are as follows: sand, loamy sand, sandy loam, loam, silt loam, silt, sandy clay loam, clay loam, silty clay loam, sandy clay, silty clay and clay. The sand, loamy sand, and sandy loam classes may be further divided by specifying "coarse," "fine," or "very fine." A coarse-textured soil is one high in sand content; a fine-textured soil is one high in clay content.

Water-holding Capacity - The ability of a soil to hold water. The capacity (or ability) of soil to hold water against gravity.

Watershed - An area of land from which all water that falls within the area converges toward and discharges past a designated point.

## TECHNICAL REFERENCES

C. E. Ramser - FLOW OF WATER IN DRAINAGE CHANNELS - U. S. Department of Agriculture - Technical Bulletin No. 129 - U. S. Government Printing Office - Washington, D. C.

H. W. King - HANDBOOK OF HYDRAULICS - McGraw-Hill Book Company, Inc., New York, N. Y.

War Department, Corps of Engineers - HYDRAULIC TABLES, U. S. Government Printing Office, Washington, D. C.

U. S. Department of Agriculture, Soil Conservation Service - NATIONAL ENGINEERING HANDBOOK - DRAINAGE - Section 16, Chapters 1,2,3,4,5, and 6.

U. S. Department of Agriculture, Soil Conservation Service - NATIONAL ENGINEERING HANDBOOK - HYDRAULICS - Section 5.

U. S. Department of Agriculture, Soil Conservation Service - FIELD DRAINAGE GUIDE FOR SOUTH CAROLINA.

U. S. Department of Commerce, Weather Bureau - TECHNICAL PAPER NO. 40 - RAINFALL FREQUENCY ATLAS OF THE UNITED STATES - U. S. Government Printing Office - Washington, D. C.

U. S. Department of Commerce, Bureau of Public Roads - HYDRAULIC CHARTS FOR THE SELECTION OF HIGHWAY CULVERTS.

U. S. Department of Agriculture, Soil Conservation Service - NATIONAL ENGINEERING HANDBOOK - HYDROLOGY - Section 4.

FEASIBILITY STUDY FOR MAIN DRAINAGE CANALS in Horry County.

FEASIBILITY STUDY FOR MAIN DRAINAGE CANALS in Williamsburg County.

WATER MANAGEMENT STUDY FOR MAIN DRAINAGE CANALS in Dorchester County.



## AUTHORITY AND ACKNOWLEDGEMENT

Authority for preparation of the Water Runoff Study for Main Drainageways and Outlets for Florence County is the result of a cooperative agreement entered into on June 7, 1973, by:

Florence County Council -

D. N. Bath, Chairman  
R. L. Poston  
J. B. McCutcheon  
Joe Griffin  
G. B. Stokes, Jr.  
Herbert T. Floyd  
Jerry Keith  
F. M. Lynch, Jr.  
Cale Yarborough

Florence Soil and Water Conservation District Commissioners -

R. D. McLendon, Chairman  
W. D. Boling  
John B. Daniels  
L. D. Eagles  
Jim R. Harwell

Soil Conservation Service - George E. Huey, State Conservationist

Administrative supervision for the Soil Conservation Service -

B. Clayton Graham - former Area Conservationist  
John S. Case - Area Conservationist

Direct responsibility for preparation of plans, designs and final report:

Calvin B. Derrick - Civil Engineer, Soil Conservation Service  
Thomas L. Hyman - Soil Conservation Technician, Soil Conservation Service  
Henry B. Watson - Soil Conservation Technician, Soil Conservation Service

Special technical assistance during all phases of the preparation of the report was given by:

W. Burton Wells, State Conservation Engineer, Soil Conservation Service  
James J. Pitts, Soil Scientist, Soil Conservation Service  
Albert H. Cole, District Conservationist, Soil Conservation Service

Others who furnished data, information, or services used in the preparation of the report:

U. S. Weather Bureau  
U. S. Department of the Interior  
South Carolina Highway Department

Assistance in typing tables, charts, and manuscript gratefully acknowledged:

Mrs. Sandra Warren, Clerk Typist, Soil Conservation Service, Florence, S. C.  
Mrs. Catherine Pate, Clerk Typist, Soil Conservation Service Area Office  
Florence, S. C.

Cartography and Printing:

Fort Worth Cartographic Unit, Soil Conservation Service, Fort Worth, Texas.

## EXPLANATION OF ENGINEERING DATA TABLES

The following Engineering Data Tables contain information, listed by areas, for each main canal and lateral watershed.

An explanation of each column in the Engineering Data Sheets is as follows:

- |           |  |
|-----------|--|
| Column 1  | CANAL NUMBER<br>Numbering of main canals begin with M-1 and laterals with L-1, in each area.   |
| Column 2  | LENGTH IN FEET<br>Stationing of all mains and laterals begins at the upper end (headwaters) and continues toward the outlet. Mains and laterals are shown in reaches or sections in the data tables for design purposes. Each reach or section reflects a change in water concentration resulting from entrance of lateral drainage. |
| Column 3  | WATERSHED IN ACRES<br>See definition of terms.   |
| Column 4  | DISCHARGE-CUBIC FEET PER SECOND<br>From appropriate drainage coefficient curves dependent on land use. (See Fig. No. 1)  |
| Column 5a | TOP WIDTH IN FEET<br>All ditches estimated on average 5' depth.  |
| Column 5b | BOTTOM WIDTH IN FEET<br>Self-explanatory.  |
| Column 6  | EXCAVATION IN CUBIC YARDS<br>Self-explanatory.   |
| Column 7  | RIGHT-OF-WAY CLEARING IN ACRES<br>Self-explanatory.  |
| COLUMN 8  | REQUIRED RIGHT-OF-WAY WIDTH IN FEET<br>Minimum width requirements for channel cross section, spoil management, berm width and maintenance access road.   |

TABLE No. 2

## SUMMARY OF ENGINEERING AND DESIGN DATA BY AREAS

Area Number	Length of Canals Feet	Excavation Cubic Yards	Right-of-way Clearing Acres
1	355,000	515,788	467.5
2	559,200	653,661	598.9
3	360,900	486,104	445.0
4	437,600	613,123	548.7
5	398,420	763,171	538.6
6	543,700	593,890	496.0
7	305,900	462,003	368.4
8	277,000	271,813	252.5
<hr/>			
County Totals	3,237,720	4,359,553	3715.6

ENGINEERING AND DESIGN DATA  
Area 1 - Florence - Mars Bluff - Quinby

CANAL No. (1)	LENGTH Ft. (2)	WATERSHED Ac. (3)	DISCHARGE c.f.s. (4)	CHANNEL DIMENSIONS		EXCAVATION Cu. Yds. (6)	RT. OF WAY CLEARING Ac. (7)	REQUIRED RT. OF WAY WIDTH Ft. (8)
				TOP WIDTH Ft. (5a)	BOTTOM WIDTH Ft. (5b)			
M-1A	1900	80	8	13	3	2812	2.6	60
L-1A	700	20	3	13	3	1036	1.0	60
L-1B	1400	40	5	13	3	2072	1.9	60
M-1B	1300	148	13	13	3	1924	1.8	60
Total-1	5300					7844	7.3	
M-2A	1300	25	3	13	3	1924	1.8	60
Total-2	1300					1924	1.8	
M-3A	3300	47	5	13	3	4884	4.5	60
M-3B	2800	119	12	13	3	4144	3.9	60
L-1A	1500	25	3	13	3	1924	2.1	60
M-3C	1200	172	15	13	3	1776	1.7	60
M-3D	2600	199	17	13	3	3848	3.6	60
Total-3	11,400					16,576	15.8	
M-4A	2300	170	15	13	3	3404	3.1	60
Total-4	2300					3404	3.1	
M-5A	700	60	7	13	3	1036	1.0	60
L-1A	2100	30	7	13	3	3106	2.9	60
M-5B	800	160	13	13	3	1184	1.1	60
Total-5	3600					5326	5.0	



ENGINEERING AND DESIGN DATA  
Area 1 - Florence - Mars Bluff - Quinby

CANAL No. (1)	LENGTH Ft. (2)	WATERSHED Ac. (3)	DISCHARGE c.f.s. (4)	CHANNEL DIMENSIONS		EXCAVATION Cu. Yds. (6)	RT. OF WAY CLEARING Ac. (7)	REQUIRED RT. OF WAY WIDTH Ft. (8)
				TOP WIDTH Ft. (5a)	BOTTOM WIDTH Ft. (5b)			
M-6A Total-6	2200 2200	127	12	13	3	3256 3256	3.0 3.0	60
M-7A M-7B M-7C Total-7	5300 1400 700 7400	228 268 310	19 23 25	13 13 13	3 3 3	7844 2072 1036 10,952	7.3 1.9 1.0 10.2	60 60 60
M-8A M-8B L-1A L-1B L-1C L-1D L-2A L-1E M-8C Total-8	5600 1900 1200 2000 900 700 2400 3300 1000 19,000	444 534 42 112 146 166 180 466 1032	35 40 4 10 13 15 16 36 72	13 13 13 13 13 13 13 13 16	3 3 3 3 3 3 3 3 6	8288 2812 1776 2960 1332 1036 3552 4884 2040 28,680	7.7 2.6 1.7 2.8 1.2 1.0 3.3 4.5 1.6 26.4	60 60 60 60 60 60 60 60 70
M-9A M-9B Total-9	1700 2200 3900	96 166	9 15	13 13	3 3	2516 3256 5772	2.3 3.0 5.3	60 60

ENGINEERING AND DESIGN DATA  
Area 1 - Florence - Mars Bluff - Quinby

CANAL No. (1)	LENGTH Ft. (2)	WATERSHED Ac. (3)	DISCHARGE c.f.s. (4)	CHANNEL DIMENSIONS		EXCAVATION Cu. Yds. (6)	RT. OF WAY CLEARING Ac. (7)	REQUIRED RT. OF WAY WIDTH Ft. (8)
				TOP WIDTH Ft. (5a)	BOTTOM WIDTH Ft. (5b)			
M-10A M-10B Total-10	1600 1300 2900	52 118	6 10	13 13	3 3	2368 1924 4292	2.2 1.8 4.0	60 60
M-11A M-11B Total-11	3200 3200	156 256	13 Present canal with proper maintenance will be adequate	13	3	4736 4736	4.4 4.4	60
M-12A M-12B Total-12	1700 1200 2900	88 116	7 12	13 13	3 3	2516 1776 4292	2.3 1.7 4.0	60 60
M-13A M-13B Total-13	2300 500 2800	48 248	10 20	13 13	3 3	3404 740 4144	3.1 .7 3.8	60 60
M-14A M-14B Total-14	3600 1300 4900	160 186	15 17	13 13	3 3	5328 1924 7252	5.0 1.8 6.8	60 60
M-15A M-15B Total-15	1300 1700 3000	40 68	3 7	13 13	3 3	1924 2516 4440	1.8 2.3 4.1	60 60

ENGINEERING AND DESIGN DATA  
Area 1 - Florence - Mars Bluff - Quinby

CANAL No. (1)	LENGTH Ft. (2)	WATERSHED Ac. (3)	DISCHARGE c.f.s. (4)	CHANNEL DIMENSIONS		EXCAVATION Cu. Yds. (6)	RT. OF WAY CLEARING Ac. (7)	REQUIRED RT. OF WAY WIDTH Ft. (8)
				TOP WIDTH Ft. (5a)	BOTTOM WIDTH Ft. (5b)			
M-16A Total-16	3400 3400	132	12	13	3	5032 5032	4.7 4.7	60
M-17A M-17B M-17C L-1A L-1B M-17D Total-17	3000 1300 800 3000 2700 700 11,500	80 192 222 135 263 509	8 16 20 15 23 40	13 13 13 13 13 13	3 3 3 3 3 3	4440 1924 1184 4440 3996 1036 17,020	4.1 1.8 1.1 4.1 3.7 1.0 15.8	60 60 60 60 60 60 60
M-18A M-18B M-18C M-18D Total-18	2100 1500 1200 1500 6300	52 84 104 148	5 8 10 14	13 13 13 13	3 3 3 3	3108 2220 1776 2220 9324	2.9 2.1 1.7 2.1 8.8	60 60 60 60 60
M-19A M-19B Total-19	2000 2400 4400	172 232	15 20	13 13	3 3	2960 3552 6512	2.8 3.3 6.1	60 60 60
M-20A M-20B L-1A L-1B M-20C Total-20	2600 300 700 2500 600 6700	140 152 36 100 276	13 17 4 11 19	13 13 13 13 13	3 3 3 3 3	3848 444 1036 3700 888 9916	3.6 .5 1.0 3.4 .8 9.3	60 60 60 60 60 60

ENGINEERING AND DESIGN DATA  
Area 1 - Florence - Mars Bluff - Quinby

CANAL No. (1)	LENGTH Ft. (2)	WATERSHED Ac. (3)	DISCHARGE c.f.s. (4)	CHANNEL DIMENSIONS		EXCAVATION Cu. Yds. (6)	RT. OF WAY CLEARING Ac. (7)	REQUIRED RT. OF WAY WIDTH Ft. (8)
				TOP WIDTH Ft. (5a)	BOTTOM WIDTH Ft. (5b)			
M-21A	2000	52	6	13	3	2960	2.8	60
M-21B	1000	100	10	13	3	1480	1.4	60
M-21C	1300	132	12	13	3	1924	1.8	60
M-21D	2000	200	17	Present canal with proper maintenance will be adequate				
L-1A	900	160	14	13	3	1332	1.2	60
L-1B	600	180	16	13	3	888	.8	60
L-1C	1600	228	18	13	3	2368	2.2	60
M-21E	2000	508	39	Present canal with proper maintenance will be adequate				
Total-21	11,400					10,952	10.2	
M-22A	800	47	5	13	3	1184	1.1	60
M-22B	400	128	13	13	3	592	.6	60
M-22C	4100	300	22	13	3	6068	5.6	60
Total-22	5300					7844	7.3	
M-23A	2400	324	26	13	3	3552	3.3	60
M-23B	2600	452	33	13	3	3848	3.6	60
M-23C	2000	537	40	13	3	2960	2.8	60
M-23D	700	549	41	13	3	1036	1.0	60
Total-23	7700					11,396	10.7	
M-24A	3300	88	9	13	3	4884	4.5	60
M-24B	1200	124	Present canal with proper maintenance will be adequate					
Total-24	4500					4884	4.5	



ENGINEERING AND DESIGN DATA  
Area 1 - Florence - Mars Bluff - Quinby

CANAL No. (1)	LENGTH Ft. (2)	WATERSHED Ac. (3)	DISCHARGE c.f.s. (4)	CHANNEL DIMENSIONS		EXCAVATION Cu. Yds. (6)	RT. OF WAY CLEARING Ac. (7)	REQUIRED RT. OF WAY WIDTH Ft. (8)
				TOP WIDTH Ft. (5a)	BOTTOM WIDTH Ft. (5b)			
M-25A M-25B Total-25	1300 1800 3100	60 104	7 10	13 13	3 3	1924 2664 4588	1.8 2.5 4.3	60 60
M-26A Total-26	3300 3300	96	10	13	3	4884 4884	4.5 4.5	60
M-27A Total-27	1400 1400	44	5	13	3	2072 2072	1.9 1.9	60
M-28A M-28B Total-28	800 1000 1800	32 56	5 6	13 13	3 3	1184 3150 4334	1.1 1.4 2.5	60 60
M-29A L-1A L-1B M-29B Total-29	1800 700 1300 1700 5500	60 28 52 140	6 3 5 13	13 13 13 13	3 3 3 3	2664 1036 1924 2516 8140	2.5 1.0 1.8 2.3 7.6	60 60 60 60
M-30A M-30B Total-30	1300 3600 4900	92 252	9 20	13 13	3 3	1924 5328 7252	1.8 5.0 6.8	60 60

ENGINEERING AND DESIGN DATA  
Area 1 - Florence - Mars Bluff - Quinby

CANAL No. (1)	LENGTH Ft. (2)	WATERSHED Ac. (3)	DISCHARGE c.f.s. (4)	CHANNEL DIMENSIONS		EXCAVATION Cu. Yds. (6)	RT. OF WAY CLEARING Ac. (7)	REQUIRED RT. OF WAY WIDTH Ft. (8)
				TOP WIDTH Ft. (5a)	BOTTOM WIDTH Ft. (5b)			
M-31A	2200	80	8	13	3	3256	3.0	60
M-31B	900	148	13	13	3	1332	1.2	60
M-31C	400	172	15	13	3	592	.6	60
M-31D	300	200	18	13	3	444	.5	60
M-31E	1100	244	20	13	3	1628	1.6	60
M-31F	1400	332	28	13	3	2072	1.9	60
M-31G	1500	404	30	13	3	2220	2.1	60
L-1A	1300	28	3	13	3	1924	1.8	60
L-1B	2100	76	8	13	3	3108	2.9	60
L-2A	1400	52	43	13	3	3848	1.9	60
M-31H	1900	572	43	13	3	2812	2.6	60
Total-31	14,500					23,236	20.1	
M-32A	1800	116	10	13	3	2664	2.5	60
M-32B	2600	248	20	13	3	3848	3.6	60
M-32C	1200	268	22	13	3	1776	1.7	60
Total-32	5600					8288	7.8	
M-33A	2500	288	24	13	3	3700	3.4	60
M-33B	3600	548	40	13	3	5328	5.0	60
L-1A	900	76	8	13	3	1332	1.2	60
L-1B	3000	164	13	13	3	4440	4.1	60
M-33C	700	744	52	13	4	1169	1.0	65
Total-33	10,700					15,969	14.7	
M-34A	5900	216	18	13	3	8732	8.1	60
Total-34	5900					8732	8.1	

ENGINEERING AND DESIGN DATA  
Area 1 - Florence - Mars Bluff - Quinby

CANAL No. (1)	LENGTH Ft. (2)	WATERSHED Ac. (3)	DISCHARGE c.f.s. (4)	CHANNEL DIMENSIONS		EXCAVATION Cu. Yds. (6)	RT. OF WAY CLEARING Ac. (7)	REQUIRED RT. OF WAY WIDTH Ft. (8)
				TOP WIDTH Ft. (5a)	BOTTOM WIDTH Ft. (5b)			
M-35A	400	132	11	13	3	592	.6	60
M-35B	1200	294	28	13	3	1776	1.7	60
M-35C	2000	562	40	13	3	2960	2.8	60
M-35D	5000	1562	90	18	8	12,050	8.8	77
M-35E	2700	1770	Present canal with proper maintenance will be adequate					
Total-35	11,300					17,378	13.9	
M-36A		398	30	Present canal with proper maintenance will be adequate				
M-36B	1400	498	32	13	3	2072	1.9	60
L-1A		100	9	Present canal with proper maintenance will be adequate				
L-1B		188	17	Present canal with proper maintenance will be adequate				
L-1C		260	22	Present canal with proper maintenance will be adequate				
L-1D		276	23	Present canal with proper maintenance will be adequate				
M-36C	2600	1074	66	16	6	5304	4.1	70
L-2A	2300	144	10	13	3	3404	3.1	60
M-36D	600	1246	80	17	7	1332	1.0	74
M-36E	800	1258	81	17	7	1776	1.3	74
Total-36	7700					13,888	11.4	
M-37A	2800	176	11	13	3	4144	3.9	60
M-37B	2500	220	17	13	3	3700	3.4	60
M-37C	1300	288	22	13	3	1924	1.8	60
L-1A	1500	112	10	13	3	2220	2.1	60
L-1B	3300	220	18	13	3	4884	4.5	60
M-37D	1700	608	42	13	3	2516	2.3	60
Total-37	13,100					19,388	18.0	

ENGINEERING AND DESIGN DATA  
Area 1 - Florence - Mars Bluff - Quinby

CANAL No. (1)	LENGTH Ft. (2)	WATERSHED Ac. (3)	DISCHARGE c.f.s. (4)	CHANNEL DIMENSIONS		EXCAVATION Cu. Yds. (6)	RT. OF WAY CLEARING Ac. (7)	REQUIRED RT. OF WAY WIDTH Ft. (8)
				TOP WIDTH Ft. (5a)	BOTTOM WIDTH Ft. (5b)			
M-38A	1800	108	11	13	3	2664	2.5	60
M-38B	2000	144	13	13	3	2960	2.8	60
Total-38	3800					5624	5.3	
M-39A	2700	148	12	13	3	3996	3.7	60
Total-39	2700					3996	3.7	
M-40A	2600	248	18	13	3	3848	3.6	60
M-40B	1700	292	22	13	3	2516	2.3	60
L-1A		292	Present canal with proper maintenance will be adequate					
L-1B		372	Present canal with proper maintenance will be adequate					
M-40C	2500	700	50	14	4	4175	3.7	65
L-2A	700	28	4	13	3	1036	1.0	60
L-2B	2700	132	12	13	3	3996	3.7	60
M-40D	1000	842	59	15	5	1850	1.6	68
Total-40	11,200					17,421	15.9	
M-41A	700	164	14	13	3	1036	1.0	60
M-41B	2600	330	23	13	3	3848	3.6	60
M-41C	3800	490	35	13	3	5624	5.2	60
Total-41	7100					10,508	9.8	



ENGINEERING AND DESIGN DATA  
Area 1 - Florence - Mars Bluff - Quinby

CANAL No. (1)	LENGTH Ft. (2)	WATERSHED Ac. (3)	DISCHARGE c.f.s. (4)	CHANNEL DIMENSIONS		EXCAVATION Cu. Yds. (6)	RT. OF WAY CLEARING Ac. (7)	REQUIRED RT. OF WAY WIDTH Ft. (8)
				TOP WIDTH Ft. (5a)	BOTTOM WIDTH Ft. (5b)			
M-42A M-42B M-42C Total-42	700 4600 2000 7300	101 321 413	10 23 33	13 13 13	3 3 3	1036 6808 2960 10,804	1.0 6.3 2.8 10.1	60 60 60
M-43A M-43B M-43C Total-43	1400 2700 1000 5100	84 280 329	8 23 27	13 13 13	3 3 3	2072 3996 1480 7548	1.9 3.7 1.4 7.0	60 60 60
M-44A M-44B M-44C Total-44	6100 1500 1300 8900	294 370 442	28 29 35	13 13 13	3 3 3	9028 2220 1924 13,172	8.4 2.1 1.8 6.6	60 60 60
M-45A M-45B Total-45	6300 3800 10,100	305 425	23 32	13 13	3 3	9324 5624 14,948	8.7 5.2 13.9	60 60
M-46A M-46B M-46C M-46D Total-46	2600 700 2000 2100 7400	216 242 296 332	18 23 25 28	13 13 13 13	3 3 3 3	3848 1036 2960 3108 10,952	3.6 1.0 2.8 2.9 10.3	60 60 60

ENGINEERING AND DESIGN DATA  
Area 1 - Florence - Mars Bluff - Quinby

CANAL No. (1)	LENGTH Ft. (2)	WATERSHED Ac. (3)	DISCHARGE c.f.s. (4)	CHANNEL DIMENSIONS		EXCAVATION Cu. Yds. (6)	RT. OF WAY CLEARING Ac. (7)	REQUIRED RT. OF WAY WIDTH Ft. (8)
				TOP WIDTH Ft. (5a)	BOTTOM WIDTH Ft. (5b)			
M-47A M-47B Total-47	1200 1800 3000	160 248	14 20	13 13	3 3	1776 2664 4440	1.7 2.5 4.2	60 60
M-48A Total-48	4600 4600	208	18	13	3	6808 6808	6.3 6.3	60
M-49A M-49B M-49C M-49D Total-49	700 1200 2300 1400 5600	36 76 212 264	4 8 18 Present canal with proper maintenance will be adequate	13 13 13	3 3 3	1036 1776 3404 6216	1.0 1.7 3.1 5.8	60 60 60
M-50A M-50B L-1A L-1B M-50C Total-50	1300 500 1200 900 1300 5200	28 40 28 43 131	12 Present canal with proper maintenance will be adequate Present canal with proper maintenance will be adequate Present canal with proper maintenance will be adequate Present canal with proper maintenance will be adequate	13 13 13	3	1924 1924	1.8 1.8	60
M-51A L-1A M-51B M-51C Total-51	1800 2800 4000 8600	200 176 708 796	17 15 50 Present canal with proper maintenance will be adequate	13 13 14	3 3 4	2664 4144 6680 13,488	2.5 3.9 6.0 12.4	60 60 65

ENGINEERING AND DESIGN DATA  
Area 1 - Florence - Mars Bluff - Quinby

CANAL No. (1)	LENGTH Ft. (2)	WATERSHED Ac. (3)	DISCHARGE c.f.s. (4)	CHANNEL DIMENSIONS		EXCAVATION Cu. Yds. (6)	RT. OF WAY CLEARING Ac. (7)	REQUIRED RT. OF WAY WIDTH Ft. (8)
				TOP WIDTH Ft. (5a)	BOTTOM WIDTH Ft. (5b)			
M-52A	700	20	2	13	3	1036	1.0	60
L-1A	2600	106	10	13	3	3848	3.6	60
L-1B	1800	134	Present canal with proper maintenance will be adequate					
M-52B	1000	198	13	13	3	1480	1.4	60
Total-52	6100					6364	6.0	
M-53A	1600	100	10	13	3	2368	2.2	60
M-53B	1800	172	16	13	3	2664	2.5	60
Total-53	3400					5032	4.7	
M-54A	2000	248	20	13	3	2960	2.8	60
M-54B	1900	448	35	13	3	2812	2.6	60
Total-54	3900					5772	5.4	
M-55A	2300	60	6	13	3	3404	3.1	60
Total-55	2300					3404	3.1	
M-56A	500	156	13	13	3	740	.7	60
M-56B	1700	252	20	13	3	2516	2.3	60
M-56C	1400	304	23	13	3	2072	1.9	60
M-56D	1100	328	25	13	3	1628	1.6	60
Total-56	4700					6956	6.5	

ENGINEERING AND DESIGN DATA  
Area 1 - Florence - Mars Bluff - Quinby

CANAL No. (1)	LENGTH Ft. (2)	WATERSHED Ac. (3)	DISCHARGE c.f.s. (4)	CHANNEL DIMENSIONS		EXCAVATION Cu. Yds. (6)	RT. OF WAY CLEARING Ac. (7)	REQUIRED RT. OF WAY WIDTH Ft. (8)
				TOP WIDTH Ft. (5a)	BOTTOM WIDTH Ft. (5b)			
M-57A	2500	116	10	13	3	3700	3.4	60
M-57B	2800	123	16	13	3	4144	3.9	60
M-57C	1900	269	22	13	3	2812	2.6	60
M-57D	1600	317	25	13	3	2368	2.2	60
Total-57	8800					13,024	12.1	
M-58A	2000	140	13	13	3	2960	2.8	60
M-58B	1800	200	17	13	3	2664	2.5	60
M-58C		248	Present canal with proper maintenance will be adequate					
Total-58	3800					5624	5.3	
M-59A	3300	180	16	13	3	4884	4.5	60
M-59B	2000	248	21	13	3	2960	2.8	60
Total-59	5300					7844	7.3	
Area-1 Grand Total	355,000					515,788	467.5	



# ENGINEERING AND DESIGN DATA

Area 2 - Timmons ville - Cartersville - Sardis - Cusaac Crossroads

CANAL No. (1)	LENGTH Ft. (2)	WATERSHED Ac. (3)	DISCHARGE c.f.s. (4)	CHANNEL DIMENSIONS		EXCAVATION Cu. Yds. (6)	RT. OF WAY CLEARING Ac. (7)	REQUIRED RT. OF WAY WIDTH Ft. (8)
				TOP WIDTH Ft. (5a)	BOTTOM WIDTH Ft. (5b)			
M-1A	2600	110	10	13	3	3848	3.6	60
M-1B	1800	182	15	13	3	2664	2.5	60
Total-1	4400					6512	6.1	
M-2A	1800	112	10	13	3	2664	2.5	60
M-2B	800	128	13	13	3	1184	1.1	60
L-1A	1600	148	14	13	3	2368	2.2	60
L-1B	1100	180	16	13	3	1628	1.6	60
M-2C	3000	404	30	13	3	4440	4.1	60
Total-2	8300					12,284	11.5	
M-3A	2100	176	15	13	3	3108	2.9	60
M-3B	1300	208	18	13	3	1924	1.8	60
M-3C	1500	220	19	13	3	2220	2.1	60
L-1A	1800	64	7	13	3	2664	2.5	60
L-1B	800	112	14	13	3	1184	1.1	60
L-1C	800	140	14	13	3	1184	1.1	60
M-3D	2500	418	33	13	3	3700	3.4	60
Total-3	10,800					15,984	14.9	
M-4A	3300	176	15	13	3	4884	4.5	60
M-4B	1200	192	18	13	3	1776	1.7	60
Total-4	4500					6660	6.2	

ENGINEERING AND DESIGN DATA  
Area 2 - Timmons ville - Cartersville - Sardis - Cusaac Crossroads

CANAL No. (1)	LENGTH Ft. (2)	WATERSHED Ac. (3)	DISCHARGE c.f.s. (4)	CHANNEL DIMENSIONS		EXCAVATION Cu. Yds. (6)	RT. OF WAY CLEARING Ac. (7)	REQUIRED RT. OF WAY WIDTH Ft. (8)
				TOP WIDTH Ft. (5a)	BOTTOM WIDTH Ft. (5b)			
M-5A M-5B Total-5	2600 4000 6600	176 364	15 Present canal with proper maintenance will be adequate	13	3	3848 3848	3.6 3.6	60
M-6A L-1A M-6B M-6C L-2A L-2B M-6D Total-6	2600 4100 900 400 700 600 200 9500	69 124 213 217 28 38 259	7 12 17 17 4 5 22	13 13 13 13 13 13 13	3 3 3 3 3 3 3	3848 6068 1332 592 1036 888 296 14,060	3.6 5.6 1.2 0.6 1.0 0.8 0.4 13.2	60 60 60 60 60 60 60 60
M-7A M-7B M-7C Total-7	300 4200 2000 6500	36 160 210	Present canal with proper maintenance will be adequate Present canal with proper maintenance will be adequate Present canal with proper maintenance will be adequate					
M-8A M-8B M-8C Total-8	2400 800 1600 4800	70 102 160	7 Present canal with proper maintenance will be adequate Present canal with proper maintenance will be adequate	13	3	3552 3552	3.3 3.3	60

ENGINEERING AND DESIGN DATA  
Area 2 - Timmons ville - Cartersville - Sardis - Cusaac Crossroads

CANAL No. (1)	LENGTH Ft. (2)	WATERSHED Ac. (3)	DISCHARGE c.f.s. (4)	CHANNEL DIMENSIONS		EXCAVATION Cu. Yds. (6)	RT. OF WAY CLEARING Ac. (7)	REQUIRED RT. OF WAY WIDTH Ft. (8)
				TOP WIDTH Ft. (5a)	BOTTOM WIDTH Ft. (5b)			
M-9A	4000	172	15	13	3	5920	5.5	60
M-9B	700	182	17	13	3	1036	1.0	60
M-9C	300	252	22	13	3	444	0.5	60
Total-9	5000					7400	7.0	
M-10A	2800	100	Present canal with proper maintenance will be adequate					
M-10B	800	115						
Total-10	3600							
M-11A	2000	292	25	13	3	444	0.4	60
M-11B	4400	532	Present canal with proper maintenance will be adequate			444	0.4	
Total-11	6400							
M-12A	2600	90	9	13	3	3848	3.6	60
M-12B	800	112	11	13	3	1184	1.1	60
Total-12	3400					5032	4.7	
M-13A	5700	117	11	13	3	8436	7.9	60
M-13B	200	125	13	13	3	296	0.4	60
Total-13	5900					8732	8.3	
M-14A	3400	280	23	13	3	5032	4.7	60
M-14B	2000	376	30	13	3	2960	2.8	60
Total-14	5400					7992	7.5	

# ENGINEERING AND DESIGN DATA

Area 2 - Timmons ville - Cartersville - Sardis - Cusaac Crossroads

CANAL No. (1)	LENGTH Ft. (2)	WATERSHED Ac. (3)	DISCHARGE c.f.s. (4)	CHANNEL DIMENSIONS		EXCAVATION Cu. Yds. (6)	RT. OF WAY CLEARING Ac. (7)	REQUIRED RT. OF WAY WIDTH Ft. (8)
				TOP WIDTH Ft. (5a)	BOTTOM WIDTH Ft. (5b)			
M-15A	800	12	Present					
L-1A	700	12	Present					
L-2A	1700	58	Present					
L-1B	2400	118	Present					
M-15B	500	140	Present					
M-15C	300	148	Present					
Total-15	6400							
M-16A	3700	128	12	13	3	5476	5.1	60
M-16B	5600	382	30	13	3	8288	7.7	60
M-16C	2000	432	34	13	3	2960	2.8	60
Total-16	11,300					16,724	15.6	
M-17A	3100	140	13	13	3	4588	4.3	60
M-17B	1400	198	17	13	3	2072	1.9	60
Total-17	4500					6660	6.2	
M-18A	5600	264	22	13	3	8288	7.7	60
L-1A	4000	104	10	13	3	5920	5.5	60
M-18B	800	420	33	13	3	1184	1.1	60
M-18C	1900	534	40	13	3	2812	2.6	60
Total-18	12,300					18,204	16.9	
M-19A	2100	44	5	13	3	3106	0.6	60
L-1A	1200	90	9	13	3	1776	1.7	60



ENGINEERING AND DESIGN DATA  
Area 2 - Timmons ville - Cartersville - Sardis - Cusaac Crossroads

CANAL No. (1)	LENGTH Ft. (2)	WATERSHED Ac. (3)	DISCHARGE c.f.s. (4)	CHANNEL DIMENSIONS		EXCAVATION Cu. Yds. (6)	RT. OF WAY CLEARING Ac. (7)	REQUIRED RT. OF WAY WIDTH Ft. (8)
				TOP WIDTH Ft. (5a)	BOTTOM WIDTH Ft. (5b)			
L-1B	3700	150	14	13	3	5476	5.1	60
M-19B	1700	214	18	13	3	2516	2.3	60
M-19C	1200	250	20	13	3	1776	1.7	60
M-19D	400	258	21	13	3	592	0.6	60
Total-19	10,300					15,242	12.0	
L-1A	2900	124	Present canal with proper maintenance will be adequate					
L-2A	3400	92						
L-1B	400	222						
M-20A	3700	170						
M-20B	2000	442						
Total-20	12,400							
M-21A	1300	88	9	13	3	1924	1.8	60
M-21B	3300	252	21	13	3	4884	4.5	60
M-21C	200	262	22	13	3	296	0.4	60
Total-21	4800					7104	6.7	
M-22A	900	102	Present canal with proper maintenance will be adequate					
M-22B	1300	155						
Total-22	2200							
M-23A	1200	16	Present canal with proper maintenance will be adequate					
Total-23	1200							

ENGINEERING AND DESIGN DATA  
Area 2 - Timmonsville - Cartersville - Sardis - Cusaac Crossroads

CANAL No. (1)	LENGTH Ft. (2)	WATERSHED Ac. (3)	DISCHARGE c.f.s. (4)	CHANNEL DIMENSIONS		EXCAVATION Cu. Yds. (6)	RT. OF WAY CLEARING Ac. (7)	REQUIRED RT. OF WAY WIDTH Ft. (8)
				TOP WIDTH Ft. (5a)	BOTTOM WIDTH Ft. (5b)			
M-24A M-24B Total-24	3400 1300 4700	140 166	13 15	13 13	3 3	5032 1924 6956	4.7 1.4 6.1	60 60
M-25A M-25B L-1A M-25C Total-25	1800 1200 800 1300 5100	96 116 12 156	9 11 2 15	13 13 13 13	3 3 3 3	2664 1776 1184 1924 7548	2.5 1.7 1.1 1.8 7.1	60 60 60 60
M-26A M-26B Total-26	1800 1600 3400	80 112	Present canal with proper maintenance will be adequate Present canal with proper maintenance will be adequate					
M-27A M-27B M-27C Total-27	1400 700 300 2400	70 92 102	7 9 10	13 13 13	3 3 3	2072 1036 444 3552	1.9 1.0 0.5 3.4	60 60 60
M-28A M-28B Total-28	3300 500 3800	212 227	18 20	13 13	3 3	4884 740 5624	4.5 0.7 5.2	60 60

ENGINEERING AND DESIGN DATA

Area 2 - Timmons ville - Cartersville - Sardis - Cusaac Crossroads

CANAL No.. (1)	LENGTH Ft. (2)	WATERSHED Ac. (3)	DISCHARGE c.f.s. (4)	CHANNEL DIMENSIONS		EXCAVATION Cu. Yds. (6)	RT. OF WAY CLEARING Ac. (7)	REQUIRED RT. OF WAY WIDTH Ft. (8)
				TOP WIDTH Ft. (5a)	BOTTOM WIDTH Ft. (5b)			
M-29A M-29B Total-29	2000 2000 4000	216 370	Present canal with proper maintenance will be adequate Present canal with proper maintenance will be adequate					
M-30A M-30B Total-30	1800 3300 5100	74 238	7 22	13 13	3 3	2664 4884 7548	2.5 4.5 7.0	60 60
M-31A L-1A M-31B M-31C Total-31	2600 2300 1200 300 6400	92 52 184 166	7 6 15 15	13 13 13 13	3 3 3 3	3848 3404 1776 444 9472	3.6 3.1 1.7 0.5 8.9	60 60 60 60
M-32A M-32B Total-32	4900 700 5600	242 256	20 22	13 13	3 3	7252 1036 8288	6.7 1.0 7.7	60 60
M-33A M-33B Total-33	4200 1300 5500	180 196	14 18	13 13	3 3	6216 1924 8140	5.8 1.8 7.6	60 60

# ENGINEERING AND DESIGN DATA

Area 2 - Timmons ville - Cartersville - Sardis - Cusaac Crossroads

CANAL No. (1)	LENGTH Ft. (2)	WATERSHED Ac. (3)	DISCHARGE c.f.s. (4)	CHANNEL DIMENSIONS		EXCAVATION Cu. Yds. (6)	RT. OF WAY CLEARING Ac. (7)	REQUIRED RT. OF WAY WIDTH Ft. (8)
				TOP WIDTH Ft. (5a)	BOTTOM WIDTH Ft. (5b)			
M-34A M-34B Total-34	2100 1600 3700	164 196	Present canal with proper maintenance will be adequate Present canal with proper maintenance will be adequate					
M-35A M-35B Total-35	3500 1300 4800	158 180	14 16	13 13	3 3	5180 1924 7104	4.8 1.8 6.6	60 60
M-36A M-36B M-36C Total-36	1200 4400 1300 6900	58 260 286	Present canal with proper maintenance will be adequate Present canal with proper maintenance will be adequate Present canal with proper maintenance will be adequate					
M-37A M-37B Total-37	2500 1000 3500	160 185	14 17	13 13	3 3	3700 1480 5180	3.4 1.4 4.8	60 60
M-38A L-1A L-1B M-38B M-38C Total-38	2000 700 1600 700 3000 8000	100 184 207 323 363	10 17 18 26 29	13 13 13 13 13	3 3 3 3 3	2960 1036 3552 1036 4440 13,024	2.8 1.0 3.3 1.0 4.1 12.2	60 60 60 60 60



ENGINEERING AND DESIGN DATA

Area 2 - Timmons ville - Cartersville - Sardis - Cusaac Crossroads

CANAL No. (1)	LENGTH Ft. (2)	WATERSHED Ac. (3)	DISCHARGE c.f.s. (4)	CHANNEL DIMENSIONS		EXCAVATION Cu. Yds. (6)	RT. OF WAY CLEARING Ac. (7)	REQUIRED RT. OF WAY WIDTH Ft. (8)
				TOP WIDTH Ft. (5a)	BOTTOM WIDTH Ft. (5b)			
M-39A	1800	40	7	13	3	2664	2.5	60
L-1A	2000	36	4	13	3	2960	2.8	60
M-39B	800	96	12	13	3	1184	1.1	60
M-39C	1300	146	15	13	3	1924	1.8	60
M-39D	1600	176	18	13	3	2368	2.2	60
Total-39	7500					11,100	10.4	
M-40A	2400	120	Present canal with proper maintenance will be adequate					
L-1A	2100	70	7	13	3	3108	2.9	60
M-40B	1200	215	Present canal with proper maintenance will be adequate					
M-40C	2800	279	Present canal with proper maintenance will be adequate					
Total-40	8500					3108	2.9	
M-41A	2000	180	17	13	3	2960	2.8	60
L-1A	1700	88	8	13	3	2516	2.3	60
M-41B	2000	353	28	13	3	2960	2.8	60
L-2A	1300	34	4	13	3	1924	1.8	60
L-2B	1400	66	7	13	3	2072	1.9	60
M-41C	800	429	34	13	3	1184	1.1	60
Total-41	9200					13,616	12.7	
M-42A	1200	59	6	13	3	1776	1.7	60
M-42B	2900	175	15	13	3	4292	4.0	60
Total-42	4100					6068	5.7	

ENGINEERING AND DESIGN DATA

Area 2 - Timmons ville - Cartersville - Sardis - Cusaac Crossroads

CANAL No. (1)	LENGTH Ft. (2)	WATERSHED Ac. (3)	DISCHARGE c.f.s. (4)	CHANNEL DIMENSIONS		EXCAVATION Cu. Yds. (6)	FT. OF WAY CLEARING Ac. (7)	REQUIRED RT. OF WAY WIDTH Ft. (8)
				TOP WIDTH Ft. (5a)	BOTTOM WIDTH Ft. (5b)			
M-43A M-43B Total-43	3900 1200 5100	78 135	8 12	13 13	3 3	5772 1776 7548	5.4 1.7 7.1	60 60
M-44A Total-44	3500 3500	132	12	13	3	5180 5180	4.8 4.8	60
M-45A Total-45	2500 2500	92	9	13	3	3700 3700	3.4 3.4	60
M-46A M-46B Total-46	1400 4500 5900	44 224	5 Present canal with proper maintenance will be adequate	13	3	2072 2072	1.9 1.9	60
M-47A Total-47	3700 3700	82	8	13	3	5476 5476	5.1 5.1	60
M-48A L-1A M-48B L-2A L-2B M-48C M-48D Total-48	4000 1300 400 600 900 500 700 8400	140 60 206 28 52 288 298	11 6 16 4 6 24 25	13 13 13 13 13 13 13	3 3 3 3 3 3 3	5920 1924 888 888 1332 740 1036 12,728	5.5 1.8 0.8 0.8 1.2 0.7 1.0 11.8	60 60 60 60 60 60 60

ENGINEERING AND DESIGN DATA  
Area 2 - Timmons ville - Cartersville - Sardis - Cusaac Crossroads

CANAL No. (1)	LENGTH Ft. (2)	WATERSHED Ac. (3)	DISCHARGE c.f.s. (4)	CHANNEL DIMENSIONS		EXCAVATION Cu. Yds. (6)	RT. OF WAY CLEARING Ac. (7)	REQUIRED RT. OF WAY WIDTH Ft. (8)
				TOP WIDTH Ft. (5a)	BOTTOM WIDTH Ft. (5b)			
M-49A M-49B Total-49	2800 600 3400	112 128	11 13	13 13	3 3	4144 888 5032	3.9 0.8 4.7	60 60
M-50A L-1A M-50B M-50C M-50D L-2A L-2B M-50E M-50F L-3A L-3B M-50G Total-50	3200 2500 500 1600 900 1600 700 500 1400 2400 4900 400 20,600	138 190 374 450 476 86 93 593 641 84 308 959	13 23 25 34 37 8 9 44 46 8 18 64	13 13 13 13 13 13 13 14 14 13 13 14	3 3 3 3 3 3 3 4 4 3 3 4	4736 3700 740 1924 1332 2368 1036 835 2338 3552 7252 668 30,481	4.4 3.4 0.7 1.8 1.2 2.2 1.0 0.7 2.0 3.3 6.7 0.5 27.9	60 60 60 60 60 60 60 65 65 60 60 65
M-51A M-51B Total-51	3700 2900 6600	296 404	Present canal with proper maintenance will be adequate Present canal with proper maintenance will be adequate					
M-52A M-52B M-52C	4100 4300 900	260 480 525	22 34 40	13 13 13	3 3 3	5476 6364 1332	5.1 5.9 1.2	60 60 60

ENGINEERING AND DESIGN DATA  
Area 2 - Timmonsville - Cartersville - Sardis - Cusaac Crossroads

CANAL No. (1)	LENGTH Ft. (2)	WATERSHED Ac. (3)	DISCHARGE c.f.s. (4)	CHANNEL DIMENSIONS		EXCAVATION Cu. Yds. (6)	RT. OF WAY CLEARING Ac. (7)	REQUIRED RT. OF WAY WIDTH Ft. (8)
				TOP WIDTH Ft. (5a)	BOTTOM WIDTH Ft. (5b)			
L-1A	4000	116	11	13	3	5920	5.5	60
M-52D	2200	755	52	14	4	3674	3.0	65
L-2A	1000	14	2	13	3	1480	1.4	60
L-3A	3000	172	Present canal with proper maintenance will be adequate					
L-3B	400	177	Present canal with proper maintenance will be adequate					
L-2B	1600	239	20	13	3	2368	2.2	60
L-2C	1300	277	Present canal with proper maintenance will be adequate					
L-2D	2100	407	Present canal with proper maintenance will be adequate					
L-2E	1700	461	Present canal with proper maintenance will be adequate					
L-2F	900	483	Present canal with proper maintenance will be adequate					
M-52E	4200	1438	90	18	8	10,122	7.4	77
L-4A	5300	214	18	13	3	7844	7.3	60
M-52F	1600	1728	100	19	9	4144	2.9	80
Total-52	38,600					48,724	41.9	
M-53A	2400	140	13	13	3	3552	3.3	60
M-53B	1700	202	17	13	3	2516	2.3	60
Total-53	4100					6068	5.6	
M-54A	1300	380	Present canal with proper maintenance will be adequate					
M-54B	4000	772	Present canal with proper maintenance will be adequate					
M-54C	5000	1484	Present canal with proper maintenance will be adequate					
M-54D	1100	1516	Present canal with proper maintenance will be adequate					
Total-54	11,400							



ENGINEERING AND DESIGN DATA

Area 2 - Timmons ville - Cartersville - Sardis - Cusaac Crossroads

CANAL No. (1)	LENGTH Ft. (2)	WATERSHED Ac. (3)	DISCHARGE c.f.s. (4)	CHANNEL DIMENSIONS		EXCAVATION Cu. Yds. (6)	RT. OF WAY CLEARING Ac. (7)	REQUIRED RT. OF WAY WIDTH Ft. (8)
				TOP WIDTH Ft. (5a)	BOTTOM WIDTH Ft. (5b)			
M-55A	300	268	Present canal with proper maintenance will be adequate					
M-55B	2000	466	Present canal with proper maintenance will be adequate					
M-55C	3400	608	Present canal with proper maintenance will be adequate					
M-55D	1300	676	Present canal with proper maintenance will be adequate					
Total-55	7000							
M-56A	600	14	2	13	3	888	0.8	60
M-56B	700	39	4	13	3	1036	1.0	60
M-56C	800	53	6	13	3	1184	1.1	60
M-56D	2400	139	13	13	3	3552	3.3	60
Total-56	4500					6660	6.2	
M-57A	5800	420	34	13	3	8584	8.0	60
M-57B	900	452	36	13	3	1332	1.2	60
Total-57	6700					9916	9.2	
M-58A	5500	412	34	13	3	8140	7.6	60
M-58B	3800	674	48	14	4	6346	5.6	65
M-58C	4600	1112	75	16	6	9384	7.3	70
M-58D	3200	1353	Present canal with proper maintenance will be adequate					
M-58E	2800	1493	Present canal with proper maintenance will be adequate					
M-58F	500	1511	Present canal with proper maintenance will be adequate					
Total-58	20,400					23,870	20.5	

ENGINEERING AND DESIGN DATA  
Area 2 - Timmons ville - Cartersville - Sardis - Cusaac Crossroads

CANAL No. (1)	LENGTH Ft. (2)	WATERSHED Ac. (3)	DISCHARGE c.f.s. (4)	CHANNEL DIMENSIONS		EXCAVATION Cu. Yds. (6)	RT. OF WAY CLEARING Ac. (7)	REQUIRED RT. OF WAY WIDTH Ft. (8)
				TOP WIDTH Ft. (5a)	BOTTOM WIDTH Ft. (5b)			
M-59A M-59B M-59C Total-59	500 1000 2400 3900	17 49 104	2 5 10	13 13 13	3 3 3	740 1776 3552 6068	0.7 1.7 3.3 5.7	60 60 60
M-60A M-60B Total-60	500 1800 2300	34 82	Present canal with proper maintenance will be adequate Present canal with proper maintenance will be adequate					
M-61A M-61B Total-61	2200 2000 2200	130 195	12 Present canal with proper maintenance will be adequate	13 13	3 3	2960 2960	2.8 2.8	60
M-62A M-62B Total-62	1400 1700 3100	54 81	6 8	13 13	3 3	2072 2516 4588	1.9 2.3 4.2	60 60
M-63A M-63B Total-63	5600 2000 7600	246 278	20 23	13 13	3 3	7844 2368 10,212	7.3 2.2 9.5	60 60
M-64A M-64B Total-64	2600 2000 4600	150 196	14 17	13 13	3 3	3448 2960 6808	3.6 2.8 6.4	60 60

ENGINEERING AND DESIGN DATA  
Area 2 - Timmons ville - Cartersville - Sardis - Cusaac Crossroads

CANAL No. (1)	LENGTH Ft. (2)	WATERSHED Ac. (3)	DISCHARGE c.f.s. (4)	CHANNEL DIMENSIONS		EXCAVATION Cu. Yds. (6)	RT. OF WAY CLEARING Ac. (7)	REQUIRED RT. OF WAY WIDTH Ft. (8)
				TOP WIDTH Ft. (5a)	BOTTOM WIDTH Ft. (5b)			
M-65A	1800	308	25	13	3	2664	2.5	60
L-1A	2600	62	6	13	3	3848	3.6	60
L-1B	1300	92	9	13	3	1924	1.8	60
M-65B	2900	712	52	14	4	4843	4.3	65
M-65C	5000	1044	70	16	6	10,200	8.0	70
Total-65	13,600					23,479	20.2	
M-66A	1100	36	3	13	3	1628	1.6	60
L-1A	5300	302	23	13	3	7844	7.3	60
L-1B	1000	318	25	13	3	1480	1.4	60
M-66B	100	360	28	13	3	148	0.3	60
M-66C	3000	470	36	13	3	4440	4.1	60
M-66D	800	491	38	13	3	1480	1.4	60
Total-66	11,300					17,020	16.1	
M-67A	1600	38	4	13	3	2368	2.2	60
L-1A	3700	280	20	13	3	5476	5.1	60
M-67B	2100	348	29	13	3	3108	2.9	60
L-2A	3400	152	14	13	3	5032	4.7	60
L-2B	3000	256	22	13	3	4440	4.1	60
M-67C	1200	734	51	14	4	2004	1.7	65
M-67D	300	742	52	14	4	668	0.4	65
Total-67	15,300					23,096	21.1	

ENGINEERING AND DESIGN DATA  
Area 2 - Timmons ville - Cartersville - Sardis - Cusaac Crossroads

CANAL No. (1)	LENGTH Ft. (2)	WATERSHEID Ac. (3)	DISCHARGE c.f.s. (4)	CHANNEL DIMENSIONS		EXCAVATION Cu. Yds. (6)	RT. OF WAY CLEARING Ac. (7)	REQUIRED RT. OF WAY WIDTH Ft. (8)
				TOP WIDTH Ft. (5a)	BOTTOM WIDTH Ft. (5b)			
M-68A M-68B Total-68	4600 300 4900	424 433	31 32	13 13	3 3	6808 444 7252	6.3 0.5 6.8	60 60
M-69A M-69B L-1A M-69C M-69D M-69E L-2A L-2B L-3A L-3B L-3C M-69F M-69G Total-69	500 2200 2600 800 500 800 1300 400 900 3300 500 1600 1600 17,000	62 119 88 241 273 302 36 44 50 146 154 550 592	6 11 Present canal with proper maintenance will be adequate 20 Present canal with proper maintenance will be adequate Present canal with proper maintenance will be adequate Present canal with proper maintenance will be adequate Present canal with proper maintenance will be adequate 5 13 14 40 42	13 13 13 13 13 13 13 13 13 13 13 13 13	3 3 3 3 3 3 3 3 3 3 3 3 3	740 3256 1184 1332 4884 740 2368 2368 16,872	0.7 3.0 1.1 1.2 4.5 0.7 2.2 2.2 15.6	60 60 60 60 60 60 60 60 60 60 60 60 60 60
M-70A M-70B M-70C M-70D M-70E Total-70	1700 3400 2200 4500 6300 18,100	72 256 322 554 790	7 21 26 41 52	13 13 13 13 14	3 3 3 3 4	2516 5032 2368 6216 10,020 26,152	2.3 4.7 2.2 5.8 8.9 23.9	60 60 60 60 65



ENGINEERING AND DESIGN DATA  
Area 2 - Timmons ville - Cartersville - Sardis - Cusaac Crossroads

CANAL No. (1)	LENGTH Ft. (2)	WATERSHED Ac. (3)	DISCHARGE c.f.s. (4)	CHANNEL DIMENSIONS		EXCAVATION Cu. Yds. (6)	RT. OF WAY CLEARING Ac. (7)	REQUIRED RT. OF WAY WIDTH Ft. (8)
				TOP WIDTH Ft. (5a)	BOTTOM WIDTH Ft. (5b)			
M-71A Total-71	6000 6000	250	20	13	3	8140 8140	7.6 7.6	60
M-72A Total-72	4500 4500	254	20	13	3	6068 6068	5.6 5.6	60
M-73A M-73B Total-73	6000 3700 9700	210 252	18 20	13 13	3 3	8880 5476 14,356	8.3 5.1 13.4	60 60
M-74A M-74B L-1A L-1B L-1C L-1D L-1E M-74C M-74D L-2A M-74E Total-74	1000 1300 2600 1100 1500 1300 1800 1300 1200 2900 1700 17,700	26 60 92 312 422 472 524 664 696 60 856	3 6 9 26 33 36 39 43 50 6 59	13 13 13 13 13 13 13 13 13 13 15	3 3 3 3 3 3 3 3 4 3 5	1480 1924 3848 1628 2220 1924 2664 1924 2004 4292 3145 27,053	1.4 1.8 3.6 1.6 2.1 1.8 2.5 1.8 1.8 4.0 2.6 25.0	60 60 60 60 60 60 60 60 75 60 68

ENGINEERING AND DESIGN DATA

Area 2 - Timmons ville - Cartersville - Sardis - Cusaac Crossroads

CANAL No. (1)	LENGTH Ft. (2)	WATERSHED Ac. (3)	DISCHARGE c.f.s. (4)	CHANNEL DIMENSIONS		EXCAVATION Cu. Yds. (6)	RT. OF WAY CLEARING Ac. (7)	REQUIRED RT. OF WAY WIDTH Ft. (8)
				TOP WIDTH Ft. (5a)	BOTTOM WIDTH Ft. (5b)			
M-75A	900	12	Present canal with proper maintenance will be adequate					
L-1A	800	18		13	3	1184	1.1	60
L-1B	800	30		13	3	1184	1.1	60
M-75B	2400	59	Present canal with proper maintenance will be adequate					
Total-75	4900					2368	2.2	
M-76A	500	72		13	3	740	0.7	60
M-76B	2800	168		13	3	4144	3.9	60
Total-76	3300					4884	4.6	
M-77A	2800	90		13	3	4144	3.9	60
M-77B	1300	158		13	3	1924	1.8	60
Total-77	4100					6068	5.7	
Area-2 Grand Total	559,200					653,661	598.9	

ENGINEERING AND DESIGN DATA  
Area 3 - Savannah Grove - Peniel - Effingham

CANAL No. (1)	LENGTH Ft. (2)	WATERSHED Ac. (3)	DISCHARGE c.f.s. (4)	CHANNEL DIMENSIONS		EXCAVATION Cu. Yds. (6)	RT. OF WAY CLEARING Ac. (7)	REQUIRED RT. OF WAY WIDTH Ft. (8)
				TOP WIDTH Ft. (5a)	BOTTOM WIDTH Ft. (5b)			
M-1A M-1B Total-1	4600 1900 6500	592 656	31 37	13 13	3 3	6808 2812 9620	6.3 2.6 8.9	60 60
M-2A M-2B L-1A L-1B M-2C M-2D Total-2	3300 2300 900 2300 1400 10,200	400 620 150 160 900 930	Present canal with proper maintenance will be adequate					
			43	13	3	4884	4.5	60
			14	13	3	3404	3.1	60
			15	13	3	1332	1.2	60
			59	13	5	4255	3.6	68
			59	13	5	2590	2.1	68
						16,465	14.5	
M-3A M-3B Total-3	4100 700 4800	226 246	19 21	13 13	3 3	6068 1036 7104	5.6 1.0 6.6	60 60
M-4A L-1A L-1B M-4B M-4C L-2A L-2B L-3A L-2C L-2D	1400 1900 2100 3700 3400 1000 1900 3900 1500 3600	152 308 376 1188 1408 48 276 288 644 824	8 25 27 75 90 5 22 23 43 53	13 13 13 16 18 13 13 13 13 13	3 3 3 6 8 3 3 3 3 3	2072 2812 3108 5548 8194 1480 2812 5772 2220 5328	1.7 2.6 2.9 5.9 6.0 1.4 2.6 5.4 2.1 5.0	60 60 60 70 77 60 60 60 60 60

ENGINEERING AND DESIGN DATA  
Area 3 - Savannah Grove - Peniel - Effingham

CANAL No. (1)	LENGTH Ft. (2)	WATERSHED Ac. (3)	DISCHARGE c.f.s. (4)	CHANNEL DIMENSIONS		EXCAVATION Cu. Yds. (6)	RT. OF WAY CLEARING Ac. (7)	REQUIRED RT. OF WAY WIDTH Ft. (8)
				TOP WIDTH Ft. (5a)	BOTTOM WIDTH Ft. (5b)			
M-4D M-4E Total-4	24,400	1080 1150	Present canal with proper maintenance will be adequate Present canal with proper maintenance will be adequate			39,346	35.6	
M-5A M-5B L-1A M-5C L-2A L-2B L-2C M-5D Total-5	7300 4600 5600 2500 3800 1900 2000 1100 28,800	460 696 288 1144 180 248 290 1514	35 50 25 75 18 20 Present canal with proper maintenance will be adequate 95	13 13 13 15 13 13 16	3 3 3 5 3 3 6	10,804 6808 8288 4625 5624 2812 2244 41,205	10.0 6.3 7.7 3.9 5.2 2.6 1.8 37.5	60 60 60 68 60 60 70
M-6A M-6B M-6C M-6D M-6E M-6F L-1A L-1B M-6G Total-6	4300 4300 5200 800 4500 1200 2000 1300 3600 27,200	539 775 1539 1579 2398 2462 272 298 3080	39 50 90 105 150 169 22 25 195	13 13 16 17 22 22 13 13 26	3 3 6 7 12 12 3 3 16	6364 6364 10,608 1776 14,175 3780 2960 1924 14,004 61,955	5.9 5.9 8.3 1.3 9.1 2.4 5.5 1.8 8.4 48.6	60 60 70 74 89 89 60 60 102

ENGINEERING AND DESIGN DATA  
Area 3 - Savannah Grove - Peniel - Effingham

CANAL No. (1)	LENGTH Ft. (2)	WATERSHED Ac. (3)	DISCHARGE c.f.s. (4)	CHANNEL DIMENSIONS		EXCAVATION Cu. Yds. (6)	RT. OF WAY CLEARING Ac. (7)	REQUIRED RT. OF WAY WIDTH Ft. (8)
				TOP WIDTH Ft. (5a)	BOTTOM WIDTH Ft. (5b)			
M-7A	2500	320	25	13	3	3700	3.4	60
M-7B	3200	516	38	13	3	4736	4.4	60
M-7C	1300	592	43	13	3	1924	1.8	60
M-7D	3300	780	59	15	5	6105	5.1	68
L-1A	1300	56	Present canal with proper maintenance will be adequate					
L-2A	5200	440						
L-1B	4200	596						
L-1C	6800	1088						
M-7E	2600	2232	130	22	12	8190	5.1	89
M-7F	2800	2412	140	24	14	9856	6.1	95
Total-7	33,200					15,700	25.9	
M-8A	3300	152	13	13	3	4884	4.5	60
Total-8	3300					4884	4.5	
M-9A	4900	428	30	13	3	7252	6.7	60
M-9B	4100	676	47	14	4	6847	6.1	65
Total-9	9000					13,320	12.8	
M-10A	1200	84	7	13	3	1776	1.7	60
M-10B	2600	212	15	13	3	3848	3.6	60
Total-10	3800					5624	5.3	



ENGINEERING AND DESIGN DATA  
Area 3 - Savannah Grove - Peniel - Effingham

CANAL No. (1)	LENGTH Ft. (2)	WATERSHED Ac. (3)	DISCHARGE c.f.s. (4)	CHANNEL DIMENSIONS		EXCAVATION Cu. Yds. (6)	RT. OF WAY CLEARING Ac. (7)	REQUIRED RT. OF WAY WIDTH Ft. (8)
				TOP WIDTH Ft. (5a)	BOTTOM WIDTH Ft. (5b)			
M-11A M-11B Total-11	5100 1900 7000	242 298	22 23	13 13	3 3	7548 2812 10,360	3.7 1.4 5.1	60 60
M-12A M-12B Total-12	3000 2600 5600	160 340	13 Present canal with proper maintenance will be adequate	13	3	4440 4440	4.1 4.1	60
M-13A M-13B L-1A L-1B M-13C M-13D M-13E Total-13	3300 4300 3200 2400 1800 3200 700 18,900	312 620 264 434 1139 1559 1587	25 43 23 38 70 99 100	13 13 13 13 16 17 17	3 3 3 3 6 7 7	4884 6364 4736 3552 3672 7104 1554 31,866	4.5 6.6 4.4 2.6 2.9 5.4 1.1 27.5	60 60 60 60 70 74 74
M-14A L-1A M-14B M-14C Total-14	7800 4900 1000 2100 15,800	336 308 713 999	26 24 50 Present canal with proper maintenance will be adequate	13 13 14	3 3 4	11,544 7252 1670 20,466	10.8 6.7 1.5 19.0	60 60 65

ENGINEERING AND DESIGN DATA  
Area 3 - Savannah Grove - Peniel - Effingham

CANAL No. (1)	LENGTH Ft. (2)	WATERSHED Ac. (3)	DISCHARGE c.f.s. (4)	CHANNEL DIMENSIONS		EXCAVATION Cu. Yds. (6)	RT. OF WAY CLEARING Ac. (7)	REQUIRED RT. OF WAY WIDTH Ft. (8)
				TOP WIDTH Ft. (5a)	BOTTOM WIDTH Ft. (5b)			
M-15A	2000	260	22	13	3	2960	2.8	60
M-15B	1600	320	25	13	3	2368	2.2	60
M-15C	2000	528	40	13	3	2960	2.8	60
M-15D	4600	812	55	13	3	6808	6.3	60
L-1A	3200	928	10	13	3	4736	4.4	60
M-15E		1088	Present canal with proper maintenance will be adequate					
Total-15	13,400					19,832	18.5	
M-16A	2600	148	12	13	3	3848	3.6	60
L-1A	6200	340	38	13	3	9176	8.6	60
M-16B	2000	620	43	13	3	2960	2.8	60
M-16C	6500	1020	65	14	4	10,855	9.0	60
M-16D	2400	1108	75	15	5	4440	3.7	68
Total-16	19,700					31,279	27.7	
M-17A	5400	360	35	13	3	7992	7.4	60
Total-17	5400					7992	7.4	
M-18A	7300	432	32	13	3	10,804	10.0	60
Total-18	7300					10,804	10.0	
M-19A	6700	512	39	13	3	9916	9.3	60
Total-19	6700					9916	9.3	

ENGINEERING AND DESIGN DATA  
Area 3 - Savannah Grove - Peniel - Effingham

CANAL No. (1)	LENGTH Ft. (2)	WATERSHED Ac. (3)	DISCHARGE c.f.s. (4)	CHANNEL DIMENSIONS		EXCAVATION Cu. Yds. (6)	RT. OF WAY CLEARING Ac. (7)	REQUIRED RT. OF WAY WIDTH Ft. (8)
				TOP WIDTH Ft. (5a)	BOTTOM WIDTH Ft. (5b)			
M-20A M-20B Total-20	2000 3800 5800	136 402	22 33	13 13	3 3	2960 5624 8584	2.8 5.2 8.0	60 60
M-21A M-21B L-1A M-21C Total-21	2600 1400 2000 1000 7000	136 196 90 316	12 25 10 35	13 13 13 13	3 3 3 3	3848 2072 2960 1480 10,360	3.6 1.9 2.8 1.4 9.7	60 60 60 60
M-22A M-22B M-22C Total-22	1000 2300 4100 7400	252 364 516	18 25 38	13 13 13	3 3 3	1480 3404 6068 10,952	1.4 3.1 5.6 10.1	60 60 60
M-23A M-23B Total-23	2000 1500 3500	126 166	Present Present	canal with proper maintenance will be adequate canal with proper maintenance will be adequate				
M-24A L-1A M-24B M-24C	2300 2600 2600 3000	88 172 444 588	9 16 35 41	13 13 13 13	3 3 3 3	3404 3848 3848 4440	3.1 3.6 3.6 4.1	60 60 60 60

ENGINEERING AND DESIGN DATA  
Area 3 - Savannah Grove - Peniel - Effingham

CANAL No. (1)	LENGTH Ft. (2)	WATERSHED Ac. (3)	DISCHARGE c.f.s. (4)	CHANNEL DIMENSIONS		EXCAVATION Cu. Yds. (6)	RT. OF WAY CLEARING Ac. (7)	REQUIRED RT. OF WAY WIDTH Ft. (8)
				TOP WIDTH Ft. (5a)	BOTTOM WIDTH Ft. (5b)			
M-24D M-24E Total-24	2000 3100 15,600	680 796	48 57	14 15	4 5	2960 4588 23,088	3.0 4.9 22.3	65 68
M-25A M-25B M-25C Total-25	2000 3800 1300 7100	260 462 507	21 35 41	13 13 13	3 3 3	2960 5624 1924 10,508	2.8 5.2 1.8 9.8	60 60 60
M-26A M-26B Total-26	2500 1800 4300	160 200	14 17	13 13	3 3	3700 2664 6364	3.4 2.5 5.9	60 60
M-27A M-27B Total-27	2600 2000 4600	685 765	49 54	14 15	4 5	4342 3700 8042	3.9 3.1 7.0	65 68
M-28A Total-28	9300 9300	572	Present canal with proper maintenance will be adequate					

ENGINEERING AND DESIGN DATA  
Area 3 - Savannah Grove - Peniel - Effingham

CANAL No. (1)	LENGTH Ft. (2)	WATERSHED Ac. (3)	DISCHARGE c.f.s. (4)	CHANNEL DIMENSIONS		EXCAVATION Cu. Yds. (6)	RT. OF WAY CLEARING Ac. (7)	REQUIRED RT. OF WAY WIDTH Ft. (8)
				TOP WIDTH Ft. (5a)	BOTTOM WIDTH Ft. (5b)			
M-29A M-29B M-29C Total-29	1200 2300 2600 6100	40 200 361	12 23 26	13 13 13	3 3 3	1776 3404 3848 9028	1.7 3.1 3.6 8.4	60 60 60
M-30A M-30B Total-30	7300 2600 9900	472 600	40 43	13 13	3 3	10,804 3848 14,652	10.0 3.6 13.6	60 60
M-31A Total-31	2600 2600	200	18	13	3	3848 3848	4.0 4.0	60
M-32A M-32B Total-32	2800 800 3600	68 138	7 11	13 13	3 3	4144 1184 5328	3.9 1.1 5.0	60 60
M-33A M-33B Total-33	1300 2000 3300	30 60	3 2	13 13	3 3	1924 2960 4884	1.8 2.8 4.6	60 60
M-34A Total-34	2000 2000	85	9	13	3	2960 2960	2.8 2.8	60



ENGINEERING AND DESIGN DATA  
Area 3 - Savannah Grove - Peniel - Effingham

CANAL No. (1)	LENGTH Ft. (2)	WATERSHED Ac. (3)	DISCHARGE c.f.s. (4)	CHANNEL DIMENSIONS		EXCAVATION Cu. Yds. (6)	RT. OF WAY CLEARING Ac. (7)	REQUIRED RT. OF WAY WIDTH Ft. (8)
				TOP WIDTH Ft. (5a)	BOTTOM WIDTH Ft. (5b)			
M-35A Total-35	5300 5300	420	Present canal with proper maintenance will be adequate					
M-36A Total-36	5300 5300	360	Present canal with proper maintenance will be adequate					
M-37A L-1A L-1B M-37B Total-37	2800 2600 1000 800 7200	224 70 102 358	23 Present canal with proper maintenance will be adequate 37 Present canal with proper maintenance will be adequate	13  13	3  3	4144  1184 5328	3.9  1.1 5.0	60  60
Area-3 Grand Total	360,900					486,104	445.0	

ENGINEERING AND DESIGN DATA  
Area 4 - Claussen - Evergreen - Willow Creek

CANAL No. (1)	LENGTH Ft. (2)	WATERSHED Ac. (3)	DISCHARGE c.f.s. (4)	CHANNEL DIMENSIONS		EXCAVATION Cu. Yds. (6)	RT. OF WAY CLEARING Ac. (7)	REQUIRED RT. OF WAY WIDTH Ft. (8)
				TOP WIDTH Ft. (5a)	BOTTOM WIDTH Ft. (5b)			
M-1A	4800	388	30	13	3	7104	6.6	60
L-1A	4900	332	28	13	3	7252	6.7	60
M-1B	4900	1240	Present canal with proper maintenance will be adequate					
M-1C	1700	1264	Present canal with proper maintenance will be adequate					
Total-1	16,300					14,356	13.3	
M-2A	4900	280	24	13	3	7252	6.7	60
M-2B	2000	322	27	13	3	2960	2.8	60
Total-2	6900					10,212	9.5	
M-3A	1200	56	7	13	3	1776	1.7	60
M-3B	3000	144	14	13	3	4440	4.1	60
Total-3	4200					6216	5.8	
M-4A	5300	436	35	13	3	8732	7.3	60
M-4B	1000	446	35	13	3	1480	1.4	60
L-1A	3900	380	Present canal with proper maintenance will be adequate					
L-1B	2400	456	Present canal with proper maintenance will be adequate					
L-1C	700	460	Present canal with proper maintenance will be adequate					
M-4C	1200	930	59	15	5	2220	1.9	68
M-4D	2100	1118	Present canal with proper maintenance will be adequate					
M-4E	500	1142	Present canal with proper maintenance will be adequate					
Total-4	17,100					12,432	10.6	

ENGINEERING AND DESIGN DATA  
Area 4 - Claussen - Evergreen - Willow Creek

CANAL No. (1)	LENGTH Ft. (2)	WATERSHED Ac. (3)	DISCHARGE c.f.s. (4)	CHANNEL DIMENSIONS		EXCAVATION Cu. Yds. (6)	RT. OF WAY CLEARING Ac. (7)	REQUIRED RT. OF WAY WIDTH Ft. (8)
				TOP WIDTH Ft. (5a)	BOTTOM WIDTH Ft. (5b)			
M-5A	1600	204	Present canal with proper maintenance will be adequate					
M-5B	600	244	Present canal with proper maintenance will be adequate					
L-1A	3300	128	Present canal with proper maintenance will be adequate					
M-5C	4000	584	Present canal with proper maintenance will be adequate					
M-5D	1300	612	Present canal with proper maintenance will be adequate					
Total-5	10,800							
M-6A	2400	76	Present canal with proper maintenance will be adequate					
L-1A	1400	36	Present canal with proper maintenance will be adequate					
M-6B	1000	128	Present canal with proper maintenance will be adequate					
L-2A	1000	84	Present canal with proper maintenance will be adequate					
M-6C	700	328	Present canal with proper maintenance will be adequate					
M-6D	600	344	Present canal with proper maintenance will be adequate					
Total-6	7100							
M-7A	3000	140	14	13	3	4440	4.1	60
M-7B	4900	352	27	13	3	7252	6.7	60
M-7C	1400	400	30	13	3	2072	1.9	60
Total-7	9300					13,764	12.7	
M-8A	2500	160	15	13	3	3700	3.4	60
M-8B	1500	220	19	13	3	2220	2.1	60
Total-8	4000					5920	5.5	

ENGINEERING AND DESIGN DATA  
Area 4 - Claussen - Evergreen - Willow Creek

CANAL No. (1)	LENGTH Ft. (2)	WATERSHED Ac. (3)	DISCHARGE c.f.s. (4)	CHANNEL DIMENSIONS		EXCAVATION Cu. Yds. (6)	RT. OF WAY CLEARING Ac. (7)	REQUIRED RT. OF WAY WIDTH Ft. (8)
				TOP WIDTH Ft. (5a)	BOTTOM WIDTH Ft. (5b)			
M-9A	4200	311	23	13	3	6216	5.8	60
M-9B	2200	447	35	13	3	3256	3.0	60
L-1A	600	80	8	13	3	888	0.8	60
L-1B	1300	108	10	13	3	1924	1.8	60
M-9C	800	623	48	14	4	1336	1.2	65
M-9D	1900	811	59	15	5	3515	3.0	68
M-9E	3300	947	62	16	6	6732	5.3	70
L-2A	3200	300	25	13	3	4736	4.4	60
M-9F	2200	1463	90	18	8	5302	3.9	77
Total-9	19,700					33,905	29.2	
M-10A	1700	640	43	13	3	2516	2.3	60
M-10B	4000	980	61	16	6	8160	6.4	70
Total-10	5700					10,676	8.7	
M-11A	2100	165	18	13	3	3108	2.9	60
M-11B	3000	345	30	13	3	4440	4.1	60
L-1A	1300	56	27	13	3	1924	1.8	60
L-1B	2500	112	11	13	3	3700	3.4	60
M-11C	2200	645	59	15	5	4070	3.4	68
Total-11	11,100					17,242	15.6	
M-12A	2600	176	17	13	3	3848	3.6	60
M-12B	1700	336	27	13	3	2516	2.3	60
Total-12	4300					6364	5.9	

ENGINEERING AND DESIGN DATA  
Area 4 - Claussen - Evergreen - Willow Creek

CANAL No. (1)	LENGTH Ft. (2)	WATERSHED Ac. (3)	DISCHARGE c.f.s. (4)	CHANNEL DIMENSIONS		EXCAVATION Cu. Yds. (6)	RT. OF WAY CLEARING Ac. (7)	REQUIRED RT. OF WAY WIDTH Ft. (8)
				TOP WIDTH Ft. (5a)	BOTTOM WIDTH Ft. (5b)			
M-13A	2700	120	12	13	3	3996	3.7	60
M-13B	600	140	14	13	3	888	0.8	60
M-13C	700	158	15	13	3	1036	1.0	60
Total-13	4000					5920	5.5	
M-14A	3000	108	10	13	3	4440	4.1	60
M-14B	800	124	13	13	3	1184	1.1	60
Total-14	3800					5624	5.2	
M-15A	2600	100	10	13	3	3848	3.6	60
L-1A	1200	80	8	13	3	1776	1.7	60
L-1B	3000	170	15	13	3	4440	4.1	60
M-15B	1400	298	24	13	3	2072	1.9	60
M-15C	1000	338	27	13	3	1480	1.4	60
Total-15	9200					13,616	12.7	
M-16A	1300	39	5	13	3	1924	1.8	60
M-16B	1000	59	6	13	3	1480	1.4	60
Total-16	2300					3404	3.2	
M-17A	1300	80	8	13	3	1924	1.8	60
M-17B	700	98	10	13	3	1036	1.0	60
Total-17	2000					2960	2.8	



ENGINEERING AND DESIGN DATA  
Area 4 - Claussen - Evergreen - Willow Creek

CANAL No. (1)	LENGTH Ft. (2)	WATERSHED Ac. (3)	DISCHARGE c.f.s. (4)	CHANNEL DIMENSIONS		EXCAVATION Cu. Yds. (6)	RT. OF WAY CLEARING Ac. (7)	REQUIRED RT. OF WAY WIDTH Ft. (8)
				TOP WIDTH Ft. (5a)	BOTTOM WIDTH Ft. (5b)			
M-18A M-18B M-18C Total-18	4300 2000 1000 7300	280 416 456	23 33 34	13 13 13	3 3 3	6364 2960 1480 10,804	5.9 2.8 1.4 10.1	60 60 60
M-19A M-19B Total-19	2600 1100 3700	132 156	13 15	13 13	3 3	3848 1628 5476	3.6 1.6 5.2	60 60
M-20A M-20B M-20C Total-20	300 4300 2500 7100	52 412 532	6 31 41	13 13 13	3 3 3	444 6364 3700 10,508	0.5 5.9 3.4 9.8	60 60 60
M-21A L-1A L-1B M-21B Total-21	4000 2600 2500 2700 11,800	148 324 458 778	14 27 35 52	13 13 13 14	3 3 3 4	5920 3848 3700 4509 17,977	5.5 3.6 3.4 4.0 16.5	60 60 60 65
M-22A M-22B M-22C M-22D Total-22	700 1000 3800 1300 6800	208 252 524 556	18 21 41 42	13 13 13 13	3 3 3 3	1036 1480 5624 1924 10,064	1.0 1.4 5.2 1.8 9.4	60 60 60 60

ENGINEERING AND DESIGN DATA  
Area 4 - Claussen - Evergreen - Willow Creek

CANAL No. (1)	LENGTH Ft. (2)	WATERSHED Ac. (3)	DISCHARGE c.f.s. (4)	CHANNEL DIMENSIONS		EXCAVATION Cu. Yds. (6)	RT. OF WAY CLEARING Ac. (7)	REQUIRED RT. OF WAY WIDTH Ft. (8)
				TOP WIDTH Ft. (5a)	BOTTOM WIDTH Ft. (5b)			
M-23A	2100	430	35	13	3	3106	2.9	60
M-23B	2100	630	42	13	3	3106	2.9	60
M-23C	2000	750	50	14	4	3340	3.1	65
M-23D	2000	890	59	15	5	3700	3.1	68
L-1A	1500	80	8	13	3	2220	2.1	60
L-1B	4200	320	25	13	3	6216	5.8	60
M-23E	800	1398	85	17	7	1776	1.3	74
M-23F	4100	1746	100	19	9	10,619	7.5	80
M-23G	1000	1764	100	19	9	2590	1.8	80
L-2A	5600	416	31	13	3	8288	7.7	60
M-23H	1300	2220	125	22	12	4095	2.6	89
Total-23	26,700					49,056	40.8	
M-24A	1900	200	18	13	3	2812	2.6	60
L-1A	3700	152	15	13	3	5476	5.1	60
M-24B	1200	400	30	13	3	1776	1.7	60
L-2A	3000	124	12	13	3	4440	4.1	60
M-24C	2800	864	61	16	6	5712	4.4	70
M-24D	2400	936	62	16	6	4896	3.9	70
Total-24	15,000					25,112	21.8	
M-25A	3600	356	28	13	3	5328	5.0	60
M-25B	1100	436	34	13	3	1628	1.6	60
M-25C	1200	496	38	13	3	1776	1.7	60
Total-25	5900					8732	8.3	

ENGINEERING AND DESIGN DATA  
Area 4 - Claussen - Evergreen - Willow Creek

CANAL No. (1)	LENGTH Ft. (2)	WATERSHED Ac. (3)	DISCHARGE c.f.s. (4)	CHANNEL DIMENSIONS		EXCAVATION Cu. Yds. (6)	RT. OF WAY CLEARING Ac. (7)	REQUIRED RT. OF WAY WIDTH Ft. (8)
				TOP WIDTH Ft. (5a)	BOTTOM WIDTH Ft. (5b)			
M-26A	3000	200	18	13	3	4440	4.1	60
M-26B	900	272	22	13	3	1332	1.2	60
L-1A	1400	68	7	13	3	2072	1.9	60
L-1B	2500	128	12	13	3	3700	3.5	60
M-26C	5700	868	59	15	5	10,545	8.9	68
M-26D	3400	1028	69	14	4	5678	5.0	65
M-26E	1200	1076	70	14	4	2004	1.8	65
L-2A	4100	184	18	13	3	6068	5.6	60
L-2B	1000	200	22	13	3	1480	1.4	60
M-26F	1000	1304	90	16	6	2040	1.6	70
M-26G	2800	2018	Present canal with proper maintenance will be adequate					
M-26H	3800	2707	Present canal with proper maintenance will be adequate					
Total-26	30,800					39,359	35.0	
M-27A	1900	108	10	13	3	2812	2.6	60
M-27B	600	122	11	13	3	888	0.8	60
Total-27	2500					3700	3.4	
M-28A	4300	304	24	13	3	6364	5.9	60
L-1A	1000	64	6	13	3	1480	1.4	60
L-1B	700	92	9	13	3	1036	1.0	60
L-1C	3800	324	26	13	3	5624	5.2	60
M-28B	1200	848	50	14	4	2004	1.8	65
M-28C	4000	1212	Present canal with proper maintenance will be adequate					
L-2A	3600	100	10	13	3	5328	5.0	60
L-3A	1900	72	7	13	3	2812	2.6	60
L-2B	500	208	14	13	3	740	0.7	60

ENGINEERING AND DESIGN DATA  
Area 4 - Claussen - Evergreen - Willow Creek

CANAL No. (1)	LENGTH Ft. (2)	WATERSHED Ac. (3)	DISCHARGE c.f.s. (4)	CHANNEL DIMENSIONS		EXCAVATION Cu. Yds. (6)	RT. OF WAY CLEARING Ac. (7)	REQUIRED RT. OF WAY WIDTH Ft. (8)
				TOP WIDTH Ft. (5a)	BOTTOM WIDTH Ft. (5b)			
L-2C	1400	256	18	13	3	2072	1.9	60
M-28D	1700	1558	Present canal with proper maintenance will be adequate Present canal with proper maintenance will be adequate			27,460	25.5	
M-28E	1300	1646						
Total-28	25,400							
M-29A	1700	84	9	13	3	2516	2.3	60
Total-29	1700					2516	2.3	
M-30A	5000	196	16	13	3	7400	6.9	60
Total-30	5000					7400	6.9	
M-31A	4000	368	22	13	3	5920	5.5	60
M-31B	2000	504	30	13	3	2960	2.8	60
L-1A	3300	324	28	13	3	4884	4.5	60
L-1B	3300	464	42	13	3	4884	4.5	60
L-2A	3000	340	28	13	3	4440	4.1	60
L-2B	1300	390	29	13	3	1924	1.8	60
L-1C	7300	1434	90	16	6	14,892	11.7	70
L-1D	3600	1614	100	16	6	7344	5.8	70
M-31C	1200	2190	120	17	7	2664	2.0	74
Total-31	29,000					49,912	42.7	

ENGINEERING AND DESIGN DATA  
Area 4 - Claussen - Evergreen - Willow Creek

CANAL No. (1)	LENGTH Ft. (2)	WATERSHED Ac. (3)	DISCHARGE c.f.s. (4)	CHANNEL DIMENSIONS		EXCAVATION Cu. Yds. (6)	RT. OF WAY CLEARING Ac. (7)	REQUIRED RT. OF WAY WIDTH Ft. (8)
				TOP WIDTH Ft. (5a)	BOTTOM WIDTH Ft. (5b)			
M-32A M-32B Total-32	1500 1300 2800	68 108	6 10	13 13	3 3	2220 1924 4144	2.1 1.8 3.9	60 60
M-33A L-1A L-1B L-1C M-33B M-33C M-33D Total-33	3100 3300 500 1200 1800 1800 1200 12,900	280 104 116 146 520 596 656	23 10 10 13 39 42 46	13 13 13 13 13 13 14	3 3 3 3 3 3 4	4588 4884 740 1776 2664 2664 2004 19,320	4.3 4.5 0.7 1.7 2.5 2.5 1.8 18.0	60 60 60 60 60 60 65
M-34A Total-34	2200 2200	116	10	13	3	3256 3256	3.0 3.0	60
M-35A Total-35	4600 4600	336	26	13	3	6803 6803	6.3 6.3	60
M-36A M-36B Total-36	800 4500 5300	136 420	12 31	13 13	3 3	1184 6660 7844	1.1 6.2 7.3	60 60



ENGINEERING AND DESIGN DATA  
Area 4 - Claussen - Evergreen - Willow Creek

CANAL No. (1)	LENGTH Ft. (2)	WATERSHED Ac. (3)	DISCHARGE c.f.s. (4)	CHANNEL DIMENSIONS		EXCAVATION Cu. Yds. (6)	RT. OF WAY CLEARING Ac. (7)	REQUIRED RT. OF WAY WIDTH Ft. (8)
				TOP WIDTH Ft. (5a)	BOTTOM WIDTH Ft. (5b)			
M-37A L-1A M-37B Total-37	9200 5900 800 15,900	588 280 888	40 23 64	13 13 14	3 3 4	13,616 8732 1336 23,684	12.7 8.1 1.2 22.0	60 60 65
M-38A M-38B M-38C M-38D M-38E Total-38	3800 4000 3200 3900 1500 16,400	380 650 862 1132 1168	28 46 59 72 74	13 14 15 16 16	3 4 5 6 6	5624 6680 5920 7956 3060 29,240	5.2 5.5 5.0 6.2 2.4 24.3	60 60 68 70 70
M-39A M-39B Total-39	1300 1900 3200	64 132	7 12	13 13	3 3	1924 2812 4736	1.8 2.6 4.4	60 60
M-40A M-49B L-1A M-40C Total-40	2000 700 2900 1300 6900	328 348 114 514	26 28 10 38	13 13 13 13	3 3 3 3	2960 1036 4292 1924 10,212	2.8 1.0 4.0 1.8 9.6	60 60 60 60
M-41A M-41B M-41C Total-41	2200 4000 2900 9100	144 400 544	12 31 Present canal with proper maintenance will be adequate	13 13	3 3	3256 5920 9176	3.0 5.5 8.5	60 60

ENGINEERING AND DESIGN DATA  
Area 4 - Claussen - Evergreen - Willow Creek

CANAL No. (1)	LENGTH Ft. (2)	WATERSHED Ac. (3)	DISCHARGE c.f.s. (4)	CHANNEL DIMENSIONS		EXCAVATION Cu. Yds. (6)	RT. OF WAY CLEARING Ac. (7)	REQUIRED RT. OF WAY WIDTH Ft. (8)
				TOP WIDTH Ft. (5a)	BOTTOM WIDTH Ft. (5b)			
M-42A	3300	410	31	13	3	4884	4.5	60
M-42B	5100	784	54	15	5	9435	7.9	68
Total-42	8400					14,319	12.4	
M-43A	8700	594	42	13	3	12,876	12.0	60
M-43B	3000	794	55	15	5	5550	4.7	60
L-1A	2900	278	23	13	3	4292	4.0	60
L-1B	3500	408	31	13	3	5180	4.8	60
L-1C	2600	480	38	13	3	3848	3.6	60
M-43C	2200	1378	88	16	6	4488	3.5	70
Total-43	22,900					36,234	32.6	
M-44A	1600	220	18	13	3	2368	2.2	60
M-44B	4500	540	42	13	3	6660	6.2	60
M-44C	1400	608	Present canal with proper maintenance will be adequate					
Total-44	7500					9028	8.4	
M-45A	3000	75	7	13	3	4440	4.1	60
Total-45	3000					4440	4.1	
Area-4 Grand Total	437,600					613,123	548.7	

ENGINEERING AND DESIGN DATA  
Area 5 - Olanta - Lake City - Scranton - Byrds Crossroads

CANAL No. (1)	LENGTH Ft. (2)	WATERSHED Ac. (3)	DISCHARGE c.f.s. (4)	CHANNEL DIMENSIONS		EXCAVATION Cu. Yds. (6)	RT. OF WAY CLEARING Ac. (7)	REQUIRED RT. OF WAY WIDTH Ft. (8)
				TOP WIDTH Ft. (5a)	BOTTOM WIDTH Ft. (5b)			
M-1A M-1B Total-1	700 6000 6700	30 410	4 29	13 13	3 3	1036 8880 9916	1.0 8.3 9.3	60 60
M-2A M-2B M-2C M-2D M-2E M-2F Total-2	7500 3300 1400 7900 5300 5000 30,400	976 1230 1342 2274 2866 3286	64 121 148 197 224 244	16 22 24 30 32 34	6 12 14 20 22 24	15,300 10,395 4928 36,577 26,500 26,850 120,550	12.0 6.7 3.0 20.8 16.0 15.8 74.3	70 89 95 115 132 138
M-3A M-3B M-3C M-3D M-3E Total-3	1200 3400 1700 800 3600 10,700	800 972 1014 1070 1226	55 64 67 71 77	15 16 16 16 17	5 6 6 6 7	2220 6936 3468 1632 7992 22,248	1.8 5.4 2.7 1.3 6.1 17.3	68 70 70 70 74
M-4A M-4B M-4C M-4D L-1A L-1B M-4E	3100 3500 5200 5600 5200 1200 900	250 574 1092 1672 392 412 2180	24 41 70 101 31 38 126	13 13 16 19 13 13 22	3 3 6 9 3 3 12	4588 5180 10,608 14,504 7696 1776 2835	4.3 4.8 8.3 10.2 7.2 1.7 1.8	60 60 70 80 60 60 89

ENGINEERING AND DESIGN DATA  
Area 5 - Olanta - Lake City - Scranton - Byrds Crossroads

CANAL No. (1)	LENGTH Ft. (2)	WATERSHED Ac. (3)	DISCHARGE c.f.s. (4)	CHANNEL DIMENSIONS		EXCAVATION Cu. Yds. (6)	RT. OF WAY CLEARING Ac. (7)	REQUIRED RT. OF WAY WIDTH Ft. (8)
				TOP WIDTH Ft. (5a)	BOTTOM WIDTH Ft. (5b)			
M-4F	1900	2288	130	22	12	5985	3.8	89
M-4G	4900	2660	150	24	14	17,248	10.6	95
L-2A	3400	172	15	13	3	5032	4.7	60
L-2B	5800	608	43	13	3	8584	8.0	60
L-2C	3000	668	46	14	4	5010	4.4	65
M-4H	100	3328	178	28	18	426	0.2	108
M-4I		Detailed survey required to determine extent of outlet needed into adjacent county.						
Total-4	43,800					89,472	70.0	
M-5A	4000	372	29	13	3	5920	5.5	60
M-5B	7000	772	53	15	5	12,950	10.9	68
M-5C	4600	1232	77	17	7	10,212	7.8	74
Total-5	15,600					29,082	24.2	
M-6A	6600	424	32	13	3	9768	9.1	60
Total-6	6600					9768	9.1	
M-7A	2300	264	26	13	3	3404	3.2	60
M-7B	2300	476	36	13	3	3404	3.2	60
M-7C	4300	656	46	14	4	7181	6.4	65
M-7D	4900	976	64	16	6	9996	7.8	70
M-7E	4200	1196	76	16	6	8568	6.7	70
M-7F	6100	1708	102	19	9	15,799	11.2	80
M-7G	900	1728	103	19	9	2331	1.6	80
L-1A	1000	33	4	13	3	1480	1.4	60
L-1B	2100	129	12	13	3	3108	2.9	60
L-1C	6900	381	31	13	3	10,212	9.5	60

ENGINEERING AND DESIGN DATA  
Area 5 - Olanta - Lake City - Scranton - Byrds Crossroads

CANAL No. (1)	LENGTH Ft. (2)	WATERSHED Ac. (3)	DISCHARGE c.f.s. (4)	CHANNEL DIMENSIONS		EXCAVATION Cu. Yds. (6)	RT. OF WAY CLEARING Ac. (7)	REQUIRED RT. OF WAY WIDTH Ft. (8)
				TOP WIDTH Ft. (5a)	BOTTOM WIDTH Ft. (5b)			
M-7H	800	2149	124	22	12	2520	1.6	89
M-7I	2900	2485	139	24	14	10,208	6.3	95
M-7J	1200	2557	143	24	14	4224	2.6	95
L-2A	1600	100	10	13	3	2368	2.2	60
L-2B	4500	252	21	13	3	6660	6.2	60
L-2C	3300	404	31	13	3	4884	4.5	60
L-2D	900	448	34	13	3	1332	1.2	60
M-7K	1000	3057	167	26	16	3890	2.3	102
M-7L	3300	3373	187	28	18	14,058	8.1	108
Total-7	54,500					115,627	88.9	
M-8A	4200	472	36	13	3	6216	5.8	60
M-8B	2400	636	45	14	4	4008	3.5	65
M-8C	2100	732	51	14	4	3507	3.1	65
M-8D	2000	904	60	16	6	4080	3.2	70
M-8E	5300	1296	82	17	7	11,766	9.0	74
M-8F	900	1320	84	17	7	1998	1.5	74
Total-8	16,900					31,575	26.1	
M-9A	1800	164	16	13	3	2664	2.5	60
M-9B	4500	640	45	14	4	7515	6.7	65
M-9C	2800	1030	68	16	6	5712	4.4	70
M-9D	2600	1420	89	18	8	6266	4.5	77
M-9E	4000	2072	122	22	12	12,600	8.1	89
Total-9	15,700					34,757	26.2	



ENGINEERING AND DESIGN DATA  
Area 5 - Olanta - Lake City - Scranton - Byrds Crossroads

CANAL No. (1)	LENGTH Ft. (2)	WATERSHED Ac. (3)	DISCHARGE c.f.s. (4)	CHANNEL DIMENSIONS		EXCAVATION Cu. Yds. (6)	RT. OF WAY CLEARING Ac. (7)	REQUIRED RT. OF WAY WIDTH Ft. (8)
				TOP WIDTH Ft. (5a)	BOTTOM WIDTH Ft. (5b)			
M-10A	5100	456	35	13	3	7548	7.0	60
M-10B	4000	886	60	16	6	8160	5.5	70
M-10C	2000	1004	66	16	6	4080	2.8	70
M-10D	1900	1124	74	16	6	3876	2.6	70
M-10E	1600	1316	83	17	7	3552	2.2	74
M-10F	4900	1836	110	20	10	13,622	6.7	83
M-10G	1800	2152	125	22	12	5670	2.5	89
M-10H	6500	2672	151	24	14	22,880	14.2	95
Total-10	27,800					69,388	43.5	
M-11A	1000	196	17	13	3	1480	1.4	60
M-11B	8200	944	62	16	6	16,728	13.2	70
M-11C	3700	1236	79	17	7	8214	5.1	74
M-11D	3100	1688	103	19	9	8029	4.3	80
M-11E	5000	2400	135	24	14	17,600	6.9	95
L-1A	5200	488	36	13	3	7696	7.2	60
M-11F	2800	2648	149	24	14	9856	3.9	95
L-2A	4000	420	32	13	3	5920	5.5	60
L-2B	1600	460	35	13	3	2368	2.2	60
M-11G	3400	2968	162	26	16	13,226	4.7	102
M-11H	2700	3088	169	26	16	10,503	3.7	102
L-3A	3800	320	26	13	3	5624	5.2	60
L-3B	4300	672	47	14	4	7181	5.9	65
L-3C	2700	788	54	15	5	4995	3.7	68
M-11I	1100	3248	173	26	16	4279	1.6	102
M-11J	6000	3560	189	28	18	25,560	14.9	108
Total-11	58,600					149,259	89.4	

ENGINEERING AND DESIGN DATA  
Area 5 - Olanta - Lake City - Scranton - Byrds Crossroads

CANAL No. (1)	LENGTH Ft. (2)	WATERSHED Ac. (3)	DISCHARGE c.f.s. (4)	CHANNEL DIMENSIONS		EXCAVATION Cu. Yds. (6)	RT. OF WAY CLEARING Ac. (7)	REQUIRED RT. OF WAY WIDTH Ft. (8)
				TOP WIDTH Ft. (5a)	BOTTOM WIDTH Ft. (5b)			
M-12A	3800	316	26	13	3	5624	5.2	60
M-12B	5300	764	53	15	5	9805	7.3	68
M-12C	4500	1384	87	18	8	10,845	6.2	77
Total-12	13,600					26,274	18.7	
M-13A	4800	312	26	13	3	7104	6.6	60
M-13B	4400	764	53	15	5	8140	6.1	68
M-13C	3200	1008	67	16	6	6528	4.4	70
M-13D	3500	1132	73	16	6	7140	4.8	70
Total-13	15,900					28,912	21.9	
M-14A	4000	476	36	13	3	5920	5.5	60
M-14B	3100	788	55	15	5	5735	4.3	68
M-14C	5000	1004	66	16	6	10,200	6.9	70
M-14D	2200	1132	73	16	6	4488	3.0	70
Total-14	14,300					26,343	19.7	
M-15A		780	Present canal with proper maintenance will be adequate					
M-15B		896	Present canal with proper maintenance will be adequate					
M-15C		1216	Present canal with proper maintenance will be adequate					
M-15D		1420	Present canal with proper maintenance will be adequate					
Total-15								

ENGINEERING AND DESIGN DATA  
Area 5 - Olanta - Lake City - Scranton - Byrds Crossroads

CANAL No. (1)	LENGTH Ft. (2)	WATERSHED Ac. (3)	DISCHARGE c.f.s. (4)	CHANNEL DIMENSIONS		EXCAVATION Cu. Yds. (6)	RT. OF WAY CLEARING Ac. (7)	REQUIRED RT. OF WAY WIDTH Ft. (8)
				TOP WIDTH Ft. (5a)	BOTTOM WIDTH Ft. (5b)			
M-16A M-16B M-16C L-1A L-1B M-16D Total-16		120 396 424 1112 1164 1400	Present canal with proper maintenance will be adequate Present canal with proper maintenance will be adequate Present canal with proper maintenance will be adequate Present canal with proper maintenance will be adequate Present canal with proper maintenance will be adequate Present canal with proper maintenance will be adequate					
M-17A M-17B M-17C M-17D Total-17		492 996 1456 1832	Present canal with proper maintenance will be adequate Present canal with proper maintenance will be adequate Present canal with proper maintenance will be adequate Present canal with proper maintenance will be adequate					
M-18A M-18B M-18C M-18D Total-18		372 708 1004 1494	Present canal with proper maintenance will be adequate Present canal with proper maintenance will be adequate Present canal with proper maintenance will be adequate Present canal with proper maintenance will be adequate					
M-19 Total-19	67,320 67,320	8880	Lynches Lake - Camp Branch Watershed Canal (See Planning Area 5 text)					
Area 5 Grand Total	398,420					763,171	538.6	

# ENGINEERING AND DESIGN DATA

Area 6 - Friendfield - Coward - Highhill - Camerontown

CANAL No. (1)	LENGTH Ft. (2)	WATERSHED Ac. (3)	DISCHARGE c.f.s. (4)	CHANNEL DIMENSIONS		EXCAVATION Cu. Yds. (6)	RT. OF WAY CLEARING Ac. (7)	REQUIRED RT. OF WAY WIDTH Ft. (8)
				TOP WIDTH Ft. (5a)	BOTTOM WIDTH Ft. (5b)			
M-1A	2000	96	Present canal with proper maintenance will be adequate					
M-1B	2100	136	Present canal with proper maintenance will be adequate					
L-1A	5900	360	Present canal with proper maintenance will be adequate					
L-2A	1500	536	Present canal with proper maintenance will be adequate					
M-1C	1300	708	Present canal with proper maintenance will be adequate					
Total-1	12,800							
M-2A	4100	314	Present canal with proper maintenance will be adequate					
M-2B	1500	360	Present canal with proper maintenance will be adequate					
M-2C	2600	560	Present canal with proper maintenance will be adequate					
Total-2	8200							
M-3A	3300	236	20	13	3	4884	4.5	60
M-3B	1300	356	25	13	3	1924	1.8	60
M-3C	2100	436	36	13	3	3108	2.9	60
M-3D	1700	492	38	13	3	2510	2.3	60
Total-3	8400					12,426	11.5	
M-4A	700	260	35	13	3	1036	1.0	60
M-4B	4000	501	45	14	4	6680	6.0	65
M-4C	5900	1381	145	24	14	20,768	12.8	95
M-4D	3900	1493	170	26	16	15,171	9.1	102
L-3A	4900	373	18	13	3	7252	6.7	60
M-4E	1400	1918	190	28	18	5964	6.4	108
L-2A	2100	228	12	13	3	3108	2.9	60
L-2B	3300	453	31	13	3	5180	4.8	60
L-2C	3300	673	52	14	4	6680	4.9	65

# ENGINEERING AND DESIGN DATA

Area 6 - Friendfield - Coward - Highhill - Camerontown

CANAL No. (1)	LENGTH Ft. (2)	WATERSHED Ac. (3)	DISCHARGE c.f.s. (4)	CHANNEL DIMENSIONS		EXCAVATION Cu. Yds. (6)	RT. OF WAY CLEARING Ac. (7)	REQUIRED RT. OF WAY WIDTH Ft. (8)
				TOP WIDTH Ft. (5a)	BOTTOM WIDTH Ft. (5b)			
L-2D	3300	833	68	16	6	6732	5.3	70
M-4F	4000	2968	210	30	20	18,983	10.5	115
M-4G	2000	3448	218	32	20	10,649	5.3	115
L-1A	2300	220	15	13	3	3404	3.1	60
L-1B	2600	340	22	13	3	3848	3.6	60
L-1C	1000	370	28	13	3	1480	1.4	60
M-4H	1300	3866	255	34	24.	6981	4.1	138
M-4I	1400	3898	258	36	26	8036	4.7	146
Total-4	47,400					131,952	92.6	
M-5A	700	274	26	13	3	1036	1.0	60
M-5B	3800	514	42	13	3	5624	5.2	60
M-5C	1800	574	43	13	3	2664	2.5	60
Total-5	6300					9324	8.7	
M-6A	300	24	3	13	3	444	0.5	60
M-6B	4600	360	28	13	3	6808	6.3	60
M-6C	1000	524	Present canal with proper maintenance will be adequate					
M-6D	1600	772	Present canal with proper maintenance will be adequate					
L-2A	1300	148	13	13	3	1924	1.8	60
L-2B	2800	364	29	13	3	4144	3.9	60
L-2C	500	372	30	13	3	740	0.7	60
M-6E	600	1164	Present canal with proper maintenance will be adequate					
L-3A	1300	360	28	13	3	1924	1.8	60
L-3B	3000	524	39	13	3	4440	4.1	60
L-3C	1300	572	41	13	3	1924	1.8	60
L-3D	2000	636	Present canal with proper maintenance will be adequate					
M-6F	1600	1868	Present canal with proper maintenance will be adequate					



ENGINEERING AND DESIGN DATA  
Area 6 - Friendfield - Coward - Highhill - Camerontown

CANAL No. (1)	LENGTH Ft. (2)	WATERSHED Ac. (3)	DISCHARGE c.f.s. (4)	CHANNEL DIMENSIONS		EXCAVATION Cu. Yds. (6)	RT. OF WAY CLEARING Ac. (7)	REQUIRED RT. OF WAY WIDTH Ft. (8)
				TOP WIDTH Ft. (5a)	BOTTOM WIDTH Ft. (5b)			
L-1A	7700	1500	95	18	8	18,557	13.6	77
L-1B	5000	1812	Present	canal with proper maintenance	will be adequate			
L-1C	1600	2070	Present	canal with proper maintenance	will be adequate			
L-1D	1400	2168	Present	canal with proper maintenance	will be adequate			
L-1E	1500	2220	Present	canal with proper maintenance	will be adequate			
M-6G	700	4156	Present	canal with proper maintenance	will be adequate			
M-6H	1500	4276	Present	canal with proper maintenance	will be adequate			
Total-6	41,300					40,905	34.5	
M-7A	3600	296	Present	canal with proper maintenance	will be adequate			
M-7B	4600	624	Present	canal with proper maintenance	will be adequate			
M-7C	4000	932	Present	canal with proper maintenance	will be adequate			
M-7D	1000	976	Present	canal with proper maintenance	will be adequate			
M-7E	700	1008	Present	canal with proper maintenance	will be adequate			
M-7F	1000	1036	Present	canal with proper maintenance	will be adequate			
L-2A	5900	1388	Present	canal with proper maintenance	will be adequate			
L-2B	500	1412	Present	canal with proper maintenance	will be adequate			
L-2C	4000	1692	Present	canal with proper maintenance	will be adequate			
L-2D	1500	1964	Present	canal with proper maintenance	will be adequate			
L-2E	3300	1874	Present	canal with proper maintenance	will be adequate			
L-2F	8600	2720	Present	canal with proper maintenance	will be adequate			
M-7G	2500	1268	Present	canal with proper maintenance	will be adequate			
M-7H	3600	1644	Present	canal with proper maintenance	will be adequate			
L-1A	3800	308	Present	canal with proper maintenance	will be adequate			
L-1B	4000	528	Present	canal with proper maintenance	will be adequate			
M-7I	3200	1944	Present	canal with proper maintenance	will be adequate			
M-7J	1300	2224	Present	canal with proper maintenance	will be adequate			
L-3A	9900	756	Present	canal with proper maintenance	will be adequate			

ENGINEERING AND DESIGN DATA  
Area 6 - Friendfield - Coward - Highhill - Camerontown

CANAL No. (1)	LENGTH Ft. (2)	WATERSHED Ac. (3)	DISCHARGE c.f.s. (4)	CHANNEL DIMENSIONS		EXCAVATION Cu. Yds. (6)	RT. OF WAY CLEARING Ac. (7)	REQUIRED RT. OF WAY WIDTH Ft. (8)
				TOP WIDTH Ft. (5a)	BOTTOM WIDTH Ft. (5b)			
L-3B L-3C L-3D M-7K Total-7	2800 1800 1300 3300 76,200	868 932 964 3476	Present canal with proper maintenance will be adequate Present canal with proper maintenance will be adequate Present canal with proper maintenance will be adequate Present canal with proper maintenance will be adequate					
M-8A M-8B M-8C M-8D M-8E L-1A L-1B L-1C L-1D M-8F L-2A M-8G M-8H Total-8	3400 3300 5200 7100 2600 2500 2100 1800 1300 700 3300 2000 1600 36,900	184 324 748 1116 1184 360 536 592 644 1884 152 2208 2252	16 27 52 70 72 28 40 42 43 110 12 125 127	13 13 14 16 16 13 13 13 13 20 13 22 22	3 3 4 6 6 3 3 3 3 10 3 12 12	5032 4884 8684 14,484 5304 3700 3108 2664 1924 1946 4884 6300 5040 67,954	4.7 4.5 7.7 11.4 4.1 3.4 2.9 2.5 1.8 1.3 4.5 4.0 3.2 56.0	60 60 65 70 70 60 60 60 60 83 60 89 89
M-9A M-9B M-9C M-9D L-1A L-1B	600 4100 4600 2600 2000 2600	140 528 868 988 136 236	12 39 55 65 13 18	13 13 15 16 13 13	3 3 5 6 3 3	888 6068 8510 5304 2960 3848	0.8 5.6 7.2 4.1 2.8 3.6	60 60 68 70 60 60

ENGINEERING AND DESIGN DATA  
Area 6 - Friendfield - Coward - Highhill - Camerontown

CANAL No. (1)	LENGTH Ft. (2)	WATERSHED Ac. (3)	DISCHARGE c.f.s. (4)	CHANNEL DIMENSIONS		EXCAVATION Cu. Yds. (6)	FT. OF WAY CLEARING Ac. (7)	REQUIRED RT. OF WAY WIDTH Ft. (8)
				TOP WIDTH Ft. (5a)	BOTTOM WIDTH Ft. (5b)			
M-9E M-9F Total-9	1000 5900 23,400	1336 1620	80 100	17 19	7 9	2220 15,281 45,079	1.7 10.8 36.6	74 80
M-10A L-2A L-2B L-2C L-2D L-2E L-2F M-10B L-1A M-10C M-10D M-10E Total-10	2200 1300 600 4400 3900 2000 3000 2600 2700 4900 2000 1300 30,900	64 130 154 490 850 998 1934 2970 170 3972 4092 4124	Present canal with proper maintenance will be adequate Present canal with proper maintenance will be adequate Present canal with proper maintenance will be adequate Present canal with proper maintenance will be adequate Present canal with proper maintenance will be adequate Present canal with proper maintenance will be adequate Present canal with proper maintenance will be adequate Present canal with proper maintenance will be adequate Present canal with proper maintenance will be adequate Present canal with proper maintenance will be adequate Present canal with proper maintenance will be adequate Present canal with proper maintenance will be adequate					
M-11A M-11B M-11C L-1A L-1B L-2A L-1C L-1D M-11D M-11E L-3A	4100 3000 2600 1700 2800 3300 2300 1000 2600 3000 2300	240 328 420 272 348 272 676 696 1344 1432 176	20 26 33 23 28 22 46 48 Present canal with proper maintenance will be adequate Present canal with proper maintenance will be adequate 15	13 13 13 13 13 13 14 14	3 3 3 3 3 3 4 4	6068 4440 3848 2516 4144 4884 3841 1670	5.6 4.1 3.6 2.3 3.8 4.5 3.4 1.5	60 60 60 60 60 60 65 65

ENGINEERING AND DESIGN DATA  
Area 6 - Friendfield - Coward - Highhill - Camerontown

CANAL No. (1)	LENGTH Ft. (2)	WATERSHED Ac. (3)	DISCHARGE c.f.s. (4)	CHANNEL DIMENSIONS		EXCAVATION Cu. Yds. (6)	RT. OF WAY CLEARING Ac. (7)	REQUIRED RT. OF WAY WIDTH Ft. (8)
				TOP WIDTH Ft. (5a)	BOTTOM WIDTH Ft. (5b)			
L-3B	2100	284	24	13	3	3108	2.9	60
L-9A	2800	112	Present canal with proper maintenance will be adequate					
L-3C	5900	864	52	14	4	9853	8.8	65
L-3D	3000	964	58	15	5	5550	4.7	68
L-3E	1000	1012	59	15	5	1850	1.6	68
L-3F	4600	1156	67	16	6	9384	7.4	70
M-11F	3600	2844	Present canal with proper maintenance will be adequate					
L-4A	1800	128	11	13	3	2664	2.5	60
L-4B	700	140	14	13	3	1036	1.0	60
L-5A	1300	164	15	13	3	1924	1.8	60
L-5B	4900	524	39	13	3	7252	6.7	60
L-5C	1000	568	40	13	3	1036	1.4	60
L-5D	2300	608	43	13	3	3404	3.2	60
L-4C	5900	1900	105	19	9	15,281	10.8	80
L-4D	2800	1964	105	19	9	7252	5.1	80
M-11G	2700	5008	Present canal with proper maintenance will be adequate					
L-6A	1300	68	11	13	3	1924	1.8	60
L-6B	1800	128	33	13	3	2664	2.5	60
L-6C	6100	424	35	13	3	9028	8.4	60
L-7A	5300	276	15	13	3	7844	7.3	60
L-7B	1500	320	26	13	3	2220	2.1	60
L-7C	3800	480	35	13	3	5624	5.2	60
L-6D	2300	976	65	16	6	4692	11.7	70
L-6E	4300	1272	70	16	6	8772	6.9	70
L-6F	700	1332	80	17	7	1554	1.7	74
L-6G	3300	1436	Present canal with proper maintenance will be adequate					
M-11H	4600	6844	Present canal with proper maintenance will be adequate					
M-11I	3000	6936	Present canal with proper maintenance will be adequate					
L-8A	7900	320	Present canal with proper maintenance will be adequate					

ENGINEERING AND DESIGN DATA  
Area 6 - Friendfield - Coward - Highhill - Camerontown

CANAL No. (1)	LENGTH Ft. (2)	WATERSHED Ac. (3)	DISCHARGE c.f.s. (4)	CHANNEL DIMENSIONS		EXCAVATION Cu. Yds. (6)	RT. OF WAY CLEARING Ac. (7)	REQUIRED RT. OF WAY WIDTH Ft. (8)
				TOP WIDTH Ft. (5a)	BOTTOM WIDTH Ft. (5b)			
M-11J M-11K M-11L Total-11	2800 1500 2500 129,900	7416 7484 7540	Present canal with proper maintenance will be adequate Present canal with proper maintenance will be adequate Present canal with proper maintenance will be adequate			148,731 137.0		
M-12A M-12B Total-12	1300 2300 3600	160 230	15 18	13 13	3 3	1924 3408 5332	1.8 3.1 4.9	60 60
M-13A M-13B Total-13	1700 1900 3600	104 172	10 15	13 13	3 3	2516 2812 5328	2.3 2.6 4.9	60 60
M-14A M-14B L-2A M-14C M-14D L-1A L-1B M-14E M-14F Total-14	2000 3600 2600 1000 1600 700 4600 1000 1000 18,100	288 552 488 1096 1192 72 488 1760 1804	13 24 40 65 70 7 35 103 105	13 13 13 16 16 13 13 19 19	3 3 3 6 6 3 3 9 9	2960 5328 3848 2040 3264 1036 6808 2590 2590 30,464	2.8 5.0 3.6 1.6 2.6 1.0 6.3 1.8 1.8 26.5	60 60 60 70 70 60 60 80 80



ENGINEERING AND DESIGN DATA  
Area 6 - Friendfield - Coward - Highhill - Camerontown

CANAL No. (1)	LENGTH Ft. (2)	WATERSHED Ac. (3)	DISCHARGE c.f.s. (4)	CHANNEL DIMENSIONS		EXCAVATION Cu. Yds. (6)	RT. OF WAY CLEARING Ac. (7)	REQUIRED RT. OF WAY WIDTH Ft. (8)
				TOP WIDTH Ft. (5a)	BOTTOM WIDTH Ft. (5b)			
M-15A	2300	244	Present canal with proper maintenance will be adequate					
M-15B	4300	636	Present canal with proper maintenance will be adequate					
M-15C	3700	808	Present canal with proper maintenance will be adequate					
L-2A	3600	336	Present canal with proper maintenance will be adequate					
L-2B	2800	476	Present canal with proper maintenance will be adequate					
L-2C	1000	512	Present canal with proper maintenance will be adequate					
M-15D	2000	1388	Present canal with proper maintenance will be adequate					
L-1A	2600	176	Present canal with proper maintenance will be adequate					
L-1B	2100	272	Present canal with proper maintenance will be adequate					
M-15E	6300	2080	Present canal with proper maintenance will be adequate					
Total-15	30,700							
M-16A	4000	208	18	13	3	5920	5.5	60
L-3A	2300	212	18	13	3	3404	3.1	60
L-3B	2600	372	30	13	3	3848	3.6	60
M-16B	1300	636	Present canal with proper maintenance will be adequate					
L-2A	2000	132	13	13	3	2960	2.8	60
L-2B	800	148	14	13	3	1184	1.1	60
M-16C	3000	936	Present canal with proper maintenance will be adequate					
L-1A	800	72	7	13	3	1184	3.0	60
L-1B	3800	174	14	13	3	5624	5.2	60
M-16D	1300	1164	Present canal with proper maintenance will be adequate					
M-16E	2300	1220	Present canal with proper maintenance will be adequate					
Total-16	24,200					24,124	24.3	

ENGINEERING AND DESIGN DATA  
Area 6 - Friendfield - Coward - Highhill - Cameronstown

CANAL No. (1)	LENGTH Ft. (2)	WATERSHED Ac. (3)	DISCHARGE c.f.s. (4)	CHANNEL DIMENSIONS		EXCAVATION Cu. Yds. (6)	RT. OF WAY CLEARING Ac. (7)	REQUIRED RT. OF WAY WIDTH Ft. (8)
				TOP WIDTH Ft. (5a)	BOTTOM WIDTH Ft. (5b)			
M-17A	3600	320	25	13	3	5328	5.0	60
M-17B	3300	528	40	13	3	4884	4.5	60
L-1A	700	56	6	13	3	1036	1.0	60
L-1B	2800	156	15	13	3	4144	3.9	60
M-17C	2000	892	59	15	5	3700	3.1	68
M-17D	6900	1272	85	17	7	15,318	11.7	74
Total-17	19,300					34,410	29.2	
M-18A	700	64	10	13	3	1036	1.0	60
M-18B	5300	440	36	13	3	7844	7.3	60
L-1A	5300	368	35	13	3	7844	7.3	60
M-18C	2000	1048	70	16	6	4080	3.2	70
M-18D	3000	1358	89	18	8	7230	5.3	77
M-18E	700	1394	90	18	8	1687	1.2	77
Total-18	17,000					29,721	25.3	
M-19A	4000	296	23	13	3	5920	2.9	60
M-19B	1500	338	27	13	3	2220	1.1	60
Total-19	5500					8140	4.0	
Area 6 Grand Total	543,700					593,890	496.0	

ENGINEERING AND DESIGN DATA  
Area 7 - Hyman - Pamplico - Blossom - Salem

CANAL No. (1)	LENGTH Ft. (2)	WATERSHED Ac. (3)	DISCHARGE c.f.s. (4)	CHANNEL DIMENSIONS		EXCAVATION Cu. Yds. (6)	RT. OF WAY CLEARING Ac. (7)	REQUIRED RT. OF WAY WIDTH Ft. (8)
				TOP WIDTH Ft. (5a)	BOTTOM WIDTH Ft. (5b)			
M-1A	3000	536	40	13	3	4440	4.1	60
L-2A	2000	636	10	13	3	2960	2.8	60
M-1B	2000	836	55	15	5	3700	3.1	68
L-1A	5200	868	57	15	5	9620	8.1	68
L-1B	4300	1084	70	20	10	11,954	8.1	83
M-1C	4300	2608	150	24	14	15,136	9.4	95
Total-1	20,800					47,810	35.6	
M-2A	5000	888	56	15	5	9250	7.8	68
M-2B	4100	1100	Present canal with proper maintenance will be adequate					
Total-2	9100					9250	7.8	
M-3A	2000	456	Present canal with proper maintenance will be adequate					
M-3B	600	545	Present canal with proper maintenance will be adequate					
M-3C	2000	753	Present canal with proper maintenance will be adequate					
M-3D	2300	861	Present canal with proper maintenance will be adequate					
Total-3	6900							
M-4A	2600	162	15	13	3	3848	3.6	60
L-1A	4000	184	16	13	3	5920	5.5	60
M-4B	700	410	30	13	3	1036	1.0	60
L-2A	2500	44	4	13	3	3700	3.3	60
M-4C	3000	558	40	13	3	4440	4.1	60
Total-4	12,800					18,944	17.5	

ENGINEERING AND DESIGN DATA  
Area 7 - Hyman - Pamplico - Blossom - Salem

CANAL No. (1)	LENGTH Ft. (2)	WATERSHED Ac. (3)	DISCHARGE c.f.s. (4)	CHANNEL DIMENSIONS		EXCAVATION Cu. Yds. (6)	RT. OF WAY CLEARING Ac. (7)	REQUIRED RT. OF WAY WIDTH Ft. (8)
				TOP WIDTH Ft. (5a)	BOTTOM WIDTH Ft. (5b)			
M-5A M-5B Total-5	1900 1600 3500	152 236	14 20	13 13	3 3	2812 2368 5180	2.6 2.2 4.8	60 60
M-6A M-6B Total-6	1300 800 2100	62 88	7 9	13 13	3 3	1924 1184 3108	1.8 1.1 2.9	60 60
M-7A M-7B M-7C M-7D M-7E M-7F M-7G M-7H M-7I Total-7	4800 5600 1700 2600 1500 1900 1600 3100 700 23,500	692 1064 1240 1556 1660 1900 2052 2292 2316	49 71 80 95 100 130 140 143 145	14 16 17 18 22 22 24 24 24 24	4 6 7 8 12 12 14 14 14	8016 11,424 3774 6266 4725 5985 5280 10,912 2464 58,846	7.1 9.0 2.9 4.6 7.1 3.9 7.0 1.8 1.5 44.9	65 70 74 77 89 89 95 95 95
M-8A L-1A M-8B M-8C M-8D M-8E	3300 2600 800 7000 3600 1100	168 120 392 1512 1840 1880	15 12 30 90 110 120	13 13 13 18 20 22	3 3 3 8 10 12	4884 3848 1184 16,870 10,008 3465	4.5 3.6 1.8 12.3 6.8 2.2	60 60 60 77 83 89

ENGINEERING AND DESIGN DATA  
Area 7 - Hyman - Pamplico - Blossom - Salem

CANAL No. (1)	LENGTH Ft. (2)	WATERSHED Ac. (3)	DISCHARGE c.f.s. (4)	CHANNEL DIMENSIONS		EXCAVATION Cu. Yds. (6)	RT. OF WAY CLEARING Ac. (7)	REQUIRED RT. OF WAY WIDTH Ft. (8)
				TOP WIDTH Ft. (5a)	BOTTOM WIDTH Ft. (5b)			
L-2A M-8F M-8G M-8H Total-8	5300 3300 4000 1900 32,900	468 2820 3104 3180	Present canal with proper maintenance will be adequate Present canal with proper maintenance will be adequate Present canal with proper maintenance will be adequate Present canal with proper maintenance will be adequate			40,259	31.2	
M-9A Total-9	4000 4000	260	22	13	3	5920 5920	5.5 5.5	60
M-10A M-10B Total-10	2800 500 3300	248 260	20 21	13 13	3 3	4144 740 4884	3.9 0.7 4.6	60 60
M-11A M-11B M-11C M-11D Total-11	5000    5000	580 756 1308 2008	43 Present canal with proper maintenance will be adequate Present canal with proper maintenance will be adequate Present canal with proper maintenance will be adequate	13	3	7400 7400	6.9 6.9	60
M-12A M-12B Total-12	3600 1500 5100	325 353	25 28	13 13	3 3	5328 2220 7548	5.0 2.1 7.1	60 60



ENGINEERING AND DESIGN DATA  
Area 7 - Hyman - Pamplico - Blossom - Salem

CANAL No. (1)	LENGTH Ft. (2)	WATERSHED Ac. (3)	DISCHARGE c.f.s. (4)	CHANNEL DIMENSIONS		EXCAVATION Cu. Yds. (6)	RT. OF WAY CLEARING Ac. (7)	REQUIRED RT. OF WAY WIDTH Ft. (8)
				TOP WIDTH Ft. (5a)	BOTTOM WIDTH Ft. (5b)			
M-5A M-5B Total-5	1900 1600 3500	152 236	14 20	13 13	3 3	2812 2368 5180	2.6 2.2 4.8	60 60
M-6A M-6B Total-6	1300 800 2100	62 88	7 9	13 13	3 3	1924 1184 3108	1.8 1.1 2.9	60 60
M-7A M-7B M-7C M-7D M-7E M-7F M-7G M-7H M-7I Total-7	4800 5600 1700 2600 1500 1900 1600 3100 700 23,500	692 1064 1240 1556 1660 1900 2052 2292 2316	49 71 80 95 100 130 140 143 145	14 16 17 18 22 22 24 24 24	4 6 7 8 12 12 14 14 14	8016 11,424 3774 6266 4725 5985 5280 10,912 2464 58,846	7.1 9.0 2.9 4.6 7.1 3.9 7.0 1.8 1.5 44.9	65 70 74 77 89 89 95 95 95
M-8A L-1A M-8B M-8C M-8D M-8E	3300 2600 800 7000 3600 1100	168 120 392 1512 1840 1880	15 12 30 90 110 120	13 13 13 18 20 22	3 3 3 8 10 12	4884 3848 1184 16,870 10,008 3465	4.5 3.6 1.8 12.3 6.8 2.2	60 60 60 77 83 89

ENGINEERING AND DESIGN DATA  
Area 7 - Hyman - Pamplico - Blossom - Salem

CANAL No. (1)	LENGTH Ft. (2)	WATERSHED Ac. (3)	DISCHARGE c.f.s. (4)	CHANNEL DIMENSIONS		EXCAVATION Cu. Yds. (6)	RT. OF WAY CLEARING Ac. (7)	REQUIRED RT. OF WAY WIDTH Ft. (8)
				TOP WIDTH Ft. (5a)	BOTTOM WIDTH Ft. (5b)			
L-2A M-8F M-8G M-8H Total-8	5300 3300 4000 1900 32,900	468 2820 3104 3180	Present canal with proper maintenance will be adequate Present canal with proper maintenance will be adequate Present canal with proper maintenance will be adequate Present canal with proper maintenance will be adequate			40,259	31.2	
M-9A Total-9	4000 4000	260	22	13	3	5920 5920	5.5 5.5	60
M-10A M-10B Total-10	2800 500 3300	248 260	20 21	13 13	3 3	4144 740 4884	3.9 0.7 4.6	60 60
M-11A M-11B M-11C M-11D Total-11	5000   5000	580 756 1308 2008	43 Present canal with proper maintenance will be adequate Present canal with proper maintenance will be adequate Present canal with proper maintenance will be adequate	13	3	7400 7400	6.9 6.9	60
M-12A M-12B Total-12	3600 1500 5100	325 353	25 28	13 13	3 3	5328 2220 7548	5.0 2.1 7.1	60 60

ENGINEERING AND DESIGN DATA  
Area 7 - Hyman - Pamplico - Blossom - Salem

CANAL No. (1)	LENGTH Ft. (2)	WATERSHED Ac. (3)	DISCHARGE c.f.s. (4)	CHANNEL DIMENSIONS		EXCAVATION Cu. Yds. (6)	RT. OF WAY CLEARING Ac. (7)	REQUIRED RT. OF WAY WIDTH Ft. (8)
				TOP WIDTH Ft. (5a)	BOTTOM WIDTH Ft. (5b)			
M-13A M-13B Total-13	1600 1700 3300	124 184	12 17	13 13	3 3	2368 2516 4884	2.2 2.3 4.5	60 60
M-14A M-14B M-14C L-1A M-14D M-14E Total-14	3000 600 3100 3900 2000 1900 14,500	244 314 550 296 1114 1354	20 25 40 24 70 83	13 13 13 13 16 17	3 3 3 3 6 7	4440 888 4588 5772 4080 4218 23,986	4.1 0.8 4.3 5.4 3.2 3.2 21.0	60 60 60 60 70 74
M-15A L-1A M-15B M-15C Total-15	9900 4500 700 15,100	848 380 1274 1370	59 30 76 Present canal with proper maintenance will be adequate	15 13 16	5 3 6	19,246 6660 1428 27,334	15.4 6.2 1.1 22.7	68 60 70
M-16A M-16B Total-16	3200 1300 4500	208 256	17 Present canal with proper maintenance will be adequate	13	3	2960 2960	4.4 4.4	60
M-17A M-17B Total-17	5300 600 5900	572 596	40 41	13 13	3 3	7844 888 8732	7.3 0.8 8.1	60 60

ENGINEERING AND DESIGN DATA  
Area 7 - Hyman - Pamplico - Blossom - Salem

CANAL No. (1)	LENGTH Ft. (2)	WATERSHED Ac. (3)	DISCHARGE c.f.s. (4)	CHANNEL DIMENSIONS		EXCAVATION Cu. Yds. (6)	RT. OF WAY CLEARING Ac. (7)	REQUIRED RT. OF WAY WIDTH Ft. (8)
				TOP WIDTH Ft. (5a)	BOTTOM WIDTH Ft. (5b)			
M-18A	1800	96	9	13	3	2664	2.5	60
M-18B	3300	204	18	13	3	4884	4.5	60
M-18C	1300	244	20	13	3	1924	1.8	60
Total-18	6400					9472	8.8	
M-19A	900	64	7	13	3	1332	1.2	60
M-19B	2600	164	15	13	3	3848	3.6	60
M-19C	800	172	17	13	3	1184	0.5	60
Total-19	4300					6364	5.3	
M-20A	2600	168	Present canal with proper maintenance will be adequate					
M-20B	3000	364						
Total-20	5600							
M-21A	2500	172	Present canal with proper maintenance will be adequate					
Total-21	2500							
M-22A	1500	316	24	13	3	2220	2.1	60
L-1A	2700	76	7	13	3	3996	3.7	60
M-22B	4000	584	42	13	3	5920	5.5	60
Total-22	8200					12,136	11.3	
M-23A	1600	150	15	13	3	2960	2.2	60
M-23B	1300	210	18	13	3	1924	1.8	60
Total-23	2900					4884	4.0	

ENGINEERING AND DESIGN DATA  
Area 7 - Hyman - Pamplico - Blossom - Salem

CANAL No. (1)	LENGTH Ft. (2)	WATERSHED Ac. (3)	DISCHARGE c.f.s. (4)	CHANNEL DIMENSIONS		EXCAVATION Cu. Yds. (6)	RT. OF WAY CLEARING Ac. (7)	REQUIRED RT. OF WAY WIDTH Ft. (8)
				TOP WIDTH Ft. (5a)	BOTTOM WIDTH Ft. (5b)			
M-24A M-24B Total-24	1600 600 2200	92 104	9 10	13 13	3 3	3108 880 3988	2.2 0.8 3.0	60 60
M-25A M-25B Total-25	900 600 1500	68 88	7 9	13 13	3 3	1332 888 2220	1.2 0.8 2.0	60 60
M-26A M-26B Total-26	1500 800 2300	40 56	5 6	13 13	3 3	2220 1184 3404	2.1 1.1 3.2	60 60
M-27A M-27B Total-27	2000 1900 3900	156 204	14 18	13 13	3 3	2960 2812 5772	2.8 2.6 5.4	60 60
M-28A M-28B Total-28	1000 1500 2500	106 152	10 14	13 13	3 3	1480 2220 3700	1.4 2.1 3.5	60 60
M-29A M-29B Total-29	600 3300 3900	48 178	6 16	13 13	3 3	888 4884 5772	0.8 4.5 5.3	60 60



ENGINEERING AND DESIGN DATA  
Area 7 - Hyman - Pamplico - Blossom - Salem

CANAL No. (1)	LENGTH Ft. (2)	WATERSHED Ac. (3)	DISCHARGE c.f.s. (4)	CHANNEL DIMENSIONS		EXCAVATION Cu. Yds. (6)	RT. OF WAY CLEARING Ac. (7)	REQUIRED RT. OF WAY WIDTH Ft. (8)
				TOP WIDTH Ft. (5a)	BOTTOM WIDTH Ft. (5b)			
M-30A M-30B Total-30	4600 1300 5900	308 356	25 28	13 13	3 3	6808 1924 8732	6.3 1.8 8.1	60 60
M-31A M-31B Total-31	2400 1600 4000	236 310	20 Present canal with proper maintenance will be adequate	13	3	3552 3552	3.3 3.3	60
M-32A M-32B M-32C L-1A M-32D Total-32	1600 4000 1600 3200 700 11,100	108 513 829 106 960	10 36 52 10 62	13 13 14 15 16	3 3 4 5 6	2368 5920 2672 5920 1554 18,434	2.2 5.5 2.4 5.0 1.1 16.2	60 60 65 68 70
M-33A M-33B M-33C M-33D M-33E M-33F Total-33	2000 4600 2600 2600 700 900 13,400	152 524 904 1138 1242 1279	18 43 59 Present canal with proper maintenance will be adequate Present canal with proper maintenance will be adequate Present canal with proper maintenance will be adequate	13 13 15	3 3 5	2960 6808 4810 14,578	2.8 6.3 4.0 13.1	60 60 68

ENGINEERING AND DESIGN DATA  
Area 7 - Hyman - Pamplico - Blossom - Salem

CANAL No. (1)	LENGTH Ft. (2)	WATERSHED Ac. (3)	DISCHARGE c.f.s. (4)	CHANNEL DIMENSIONS		EXCAVATION Cu. Yds. (6)	RT. OF WAY CLEARING Ac. (7)	REQUIRED RT. OF WAY WIDTH Ft. (8)
				TOP WIDTH Ft. (5a)	BOTTOM WIDTH Ft. (5b)			
M-34A	2100	144	12	13	3	3108	2.9	60
L-1A	2500	232	18	13	3	3700	3.4	60
M-34B	3000	649	Present canal with proper maintenance will be adequate Present canal with proper maintenance will be adequate					
M-34C	800	679						
Total-34	8400					6808	6.3	
M-35A	3200	140	14	13	3	4736	2.4	60
L-3A	3000	172	16	13	3	4440	2.2	60
M-35B	3000	712	50	13	3	4440	2.2	60
L-1A	3600	252	38	13	3	5328	2.6	60
L-2A	2200	908	45	14	4	3674	1.9	60
L-2B	4300	1420	74	16	6	8772	5.9	60
L-2C	3500	1632	80	17	7	7770	5.9	74
L-1B	3200	1840	120	22	12	10,080	6.5	89
M-35C	700	2596	174	26	16	2723	1.6	102
M-35D	4100	2856	Present canal with proper maintenance will be adequate					
Total-35	30,800					51,963	19.9	
M-36A	5400	290	25	13	3	7992	7.4	60
M-36B	2700	554	40	13	3	3996	3.7	60
M-36C	2300	724	52	15	5	4255	3.6	68
M-37D	3400	940	66	16	6	6936	5.5	70
Total-37	13,800					23,179	20.2	
Area-7 Grand Total	305,900					462,003	368.4	

ENGINEERING AND DESIGN DATA  
Area 8 - Poston - Salem - Vox - Johnsonville

CANAL No. (1)	LENGTH Ft. (2)	WATERSHED Ac. (3)	DISCHARGE c.f.s. (4)	CHANNEL DIMENSIONS		EXCAVATION Cu. Yds. (6)	RT. OF WAY CLEARING Ac. (7)	REQUIRED RT. OF WAY WIDTH Ft. (8)
				TOP WIDTH Ft. (5a)	BOTTOM WIDTH Ft. (5b)			
M-1A	500	56	5	13	3	740	0.7	60
M-1B	2200	153	Present canal with proper maintenance will be adequate					
M-1C	1400	238	Present canal with proper maintenance will be adequate			740	0.7	
Total-1	4100							
M-2A	2600	280	Present canal with proper maintenance will be adequate					
M-2B	3200	406	Present canal with proper maintenance will be adequate					
Total-2	5800							
M-3A	4100	284	Present canal with proper maintenance will be adequate					
M-3B	3800	456	Present canal with proper maintenance will be adequate					
Total-3	7900							
M-4A	2600	88	9	13	3	3848	3.6	60
M-4B	2300	180	Present canal with proper maintenance will be adequate					
Total-4	4900					3848	3.6	
M-5A	3300	221	Present canal with proper maintenance will be adequate					
M-5B	1000	255	Present canal with proper maintenance will be adequate					
Total-5	4300							

ENGINEERING AND DESIGN DATA  
Area 8 - Poston - Salem - Vox - Johnsonville

CANAL No. (1)	LENGTH Ft. (2)	WATERSHED Ac. (3)	DISCHARGE c.f.s. (4)	CHANNEL DIMENSIONS		EXCAVATION Cu. Yds. (6)	RT. OF WAY CLEARING Ac. (7)	REQUIRED RT. OF WAY WIDTH Ft. (8)
				TOP WIDTH Ft. (5a)	BOTTOM WIDTH Ft. (5b)			
M-6A M-6B Total-6	4000 700 4700	372 382	Present canal with proper maintenance will be adequate Present canal with proper maintenance will be adequate					
M-7A M-7B M-7C M-7D Total-7	1000 2000 3300 500 6800	38 180 533 549	4 17 40 41	13 13 13 13	3 3 3 3	1480 2960 4884 740 10,064	1.4 2.8 4.5 0.7 9.4	60 60 60 60
M-8A M-8B L-1A L-1B M-8C Total-8	800 700 2500 400 4000 8400	136 152 96 102 398	13 15 10 10 Present canal with proper maintenance will be adequate	13 13 13 13	3 3 3 3	1184 1036 3700 592 6512	1.1 1.0 3.4 0.6 6.1	60 60 60 60
M-9A M-9B Total-9	3100 2800 5900	291 507	Present canal with proper maintenance will be adequate Present canal with proper maintenance will be adequate					
M-10A M-10B Total-10	4000 1600 5600	273 350	Present canal with proper maintenance will be adequate Present canal with proper maintenance will be adequate					

ENGINEERING AND DESIGN DATA  
Area 8 - Poston - Salem - Vox - Johnsonville

CANAL No. (1)	LENGTH Ft. (2)	WATERSHED Ac. (3)	DISCHARGE c.f.s. (4)	CHANNEL DIMENSIONS		EXCAVATION Cu. Yds. (6)	RT. OF WAY CLEARING Ac. (7)	REQUIRED RT. OF WAY WIDTH Ft. (8)
				TOP WIDTH Ft. (5a)	BOTTOM WIDTH Ft. (5b)			
M-11A M-11B Total-11	600 2300 2900	68 154	7 14	13 13	3 3	888 3404 4292	0.8 3.2 4.0	60 60
M-12A M-12B Total-12	1000 2600 3600	156 288	14 Present canal with proper maintenance will be adequate	13	3	1480 1480	1.4 1.4	60
M-13A Total-13	3400 3400	126	12	13	3	5032 5032	4.7 4.7	60
M-14A Total-14	2100 2100	130	13	13	3	3108 3108	2.9 2.9	60
M-15A M-15B Total-15	3300 2600 5900	460 520	34 40	13 13	3 3	4884 3848 8732	4.5 3.6 8.1	60 60
M-16A M-16B Total-16	900 3900 4800	33 301	4 Present canal with proper maintenance will be adequate	13	3	1332 1332	1.2 1.2	60



ENGINEERING AND DESIGN DATA  
Area 8 - Poston - Salem - Vox - Johnsonville

CANAL No. (1)	LENGTH Ft. (2)	WATERSHED Ac. (3)	DISCHARGE c.f.s. (4)	CHANNEL DIMENSIONS		EXCAVATION Cu. Yds. (6)	RT. OF WAY CLEARING Ac. (7)	REQUIRED RT. OF WAY WIDTH Ft. (8)
				TOP WIDTH Ft. (5a)	BOTTOM WIDTH Ft. (5b)			
M-17A	500	41	5	13	3	740	0.7	60
M-17B	2300	158	14	13	3	3404	3.2	60
M-17C	3300	330	Present canal with proper maintenance will be adequate					
L-4A	1500	132	13	13	3	2220	2.1	60
L-4B	4000	330	25	13	3	5920	5.5	60
L-5A	900	49	5	13	3	1332	1.2	60
L-5B	3300	134	13	13	3	4884	4.5	60
L-4C	1900	533	Present canal with proper maintenance will be adequate					
L-4D	2600	718	Present canal with proper maintenance will be adequate					
L-6A	1600	60	6	13	3	2368	2.2	60
L-6B	3200	136	13	13	3	4736	4.4	60
L-4E	2500	982	Present canal with proper maintenance will be adequate					
M-17D	2600	1520	Present canal with proper maintenance will be adequate					
M-17E	700	1556	Present canal with proper maintenance will be adequate					
M-17F	1600	1608	Present canal with proper maintenance will be adequate					
L-3A	3600	222	18	13	3	5328	5.0	60
L-3B	800	242	20	13	3	1184	1.1	60
L-3C	800	264	21	13	3	1184	1.1	60
L-3D	1200	344	28	13	3	1776	1.7	60
M-17G	1100	2008	Present canal with proper maintenance will be adequate					
L-2A	900	78	8	13	3	1332	1.2	60
L-2B	3000	198	17	13	3	4440	4.1	60
M-17H	3200	2206	Present canal with proper maintenance will be adequate					
L-1A	3300	284	25	13	3	4884	4.5	60
L-1B	4100	796	58	15	5	7585	6.4	68
L-1C	1000	832	58	15	5	1850	1.6	68
L-1D	1400	866	59	15	5	2590	2.2	68
M-17I	700	3096	Present canal with proper maintenance will be adequate					

ENGINEERING AND DESIGN DATA  
Area 8 - Poston - Salem - Vox - Johnsonville

CANAL No. (1)	LENGTH Ft. (2)	WATERSHED Ac. (3)	DISCHARGE c.f.s. (4)	CHANNEL DIMENSIONS		EXCAVATION Cu. Yds. (6)	RT. OF WAY CLEARING Ac. (7)	REQUIRED RT. OF WAY WIDTH Ft. (8)
				TOP WIDTH Ft. (5a)	BOTTOM WIDTH Ft. (5b)			
M-17J M-17K Total-17	1400 1500 60,500	3175 3219	Present canal with proper maintenance will be adequate Present canal with proper maintenance will be adequate			57,757	52.7	
M-18A M-18B Total-18	5300 400 5700	442 468	35 37	13 13	3 3	7844 592 8436	7.3 0.6 7.9	60 60
M-19A M-19B Total-19	2700 2000 4700	148 201	14 18	13 13	3 3	3996 2960 6956	3.7 2.8 6.5	60 60
M-20A M-20B M-20C Total-20	1600 1300 2500 5400	637 675 792	44 48 55	14 14 15	4 4 5	2368 1924 3700 7992	2.4 1.9 3.9 8.2	65 65 68
M-21A M-21B Total-21	1900 2300 4200	216 356	18 28	13 13	3 3	2812 3404 6216	2.6 3.2 5.8	60 60

ENGINEERING AND DESIGN DATA  
Area 8 - Poston - Salem - Vox - Johnsonville

CANAL No. (1)	LENGTH Ft. (2)	WATERSHED Ac. (3)	DISCHARGE c.f.s. (4)	CHANNEL DIMENSIONS		EXCAVATION Cu. Yds. (6)	RT. OF WAY CLEARING Ac. (7)	REQUIRED RT. OF WAY WIDTH Ft. (8)
				TOP WIDTH Ft. (5a)	BOTTOM WIDTH Ft. (5b)			
M-22A Total-22	3600 3600	302	24	13	3	5328 5328	5.0 5.0	60
M-23A Total-23	3100 3100	296	24	13	3	4588 4588	4.3 4.3	60
M-24A M-24B Total-24	2300 900 3200	112 132	12 14	13 13	3 3	3404 1332 4736	3.2 1.2 4.4	60 60
M-25A M-25B Total-25	2000 2100 4100	89 113	9 13	13 13	3 3	2960 1480 4440	2.8 2.9 5.7	60 60
M-26A M-26B Total-26	3100 1500 4600	228 288	18 23	13 13	3 3	4588 2220 6808	4.3 2.1 6.4	60 60
M-27A M-27B Total-27	6700 1300 8000	336 385	28 30	13 13	3 3	9916 1924 11,840	9.2 1.8 11.0	60 60

ENGINEERING AND DESIGN DATA  
Area 8 - Poston - Salem - Vox - Johnsonville

CANAL No. (1)	LENGTH Ft. (2)	WATERSHED Ac. (3)	DISCHARGE c.f.s. (4)	CHANNEL DIMENSIONS		EXCAVATION Cu. Yds. (6)	RT. OF WAY CLEARING Ac. (7)	REQUIRED RT. OF WAY WIDTH Ft. (8)
				TOP WIDTH Ft. (5a)	BOTTOM WIDTH Ft. (5b)			
M-28A Total-28	4900 4900	394	30	13	3	7252 7252	6.7 6.7	60
M-29A M-29B Total-29	3600 900 4500	176 200	17 19	13 15	3 5	5328 1332 6660	5.0 1.4 6.4	60 68
M-30A M-30B M-30C M-30D Total-30	3100 4600 3600 1700 13,000	256 628 837 881	20 42 58 Present canal with proper maintenance will be adequate	13 13 15	3 3 5	4588 6808 6660 18,056	4.3 6.3 5.6 16.2	60 60 68
M-31A M-31B L-1A L-1B L-2A L-2B L-1C M-31C Total-31	700 1500 1900 900 2800 400 2200 5900 16,300	82 142 96 114 225 235 559 988	8 13 10 11 18 19 40 68	13 13 13 13 13 13 13 16	3 3 3 3 3 3 3 6	1036 2220 2812 1332 4144 592 3256 12,036 27,428	1.0 2.1 2.6 1.2 3.9 0.6 3.0 9.5 23.9	60 60 60 60 60 60 60 70

ENGINEERING AND DESIGN DATA  
Area 8 - Poston - Salem - Vox - Johnsonville

CANAL No. (1)	LENGTH Ft. (2)	WATERSHED Ac. (3)	DISCHARGE c.f.s. (4)	CHANNEL DIMENSIONS		EXCAVATION Cu. Yds. (6)	RT. OF WAY CLEARING Ac. (7)	REQUIRED RT. OF WAY WIDTH Ft. (8)
				TOP WIDTH Ft. (5a)	BOTTOM WIDTH Ft. (5b)			
M-32A Total-32	1700 1700	182	16	13	3	2516 2516	2.3 2.3	60
M-33A M-33B Total-33	1800 3600 5400	70 302	7 Present canal with proper maintenance will be adequate	13	3	2664 2664	2.5 2.5	60
M-34A M-34B M-34C Total-34	4100 1300 1400 6800	305 441 517	24 34 40	13 13 13	3 3 3	6068 1924 2072 10,064	5.6 1.8 1.9 9.3	60 60 60
M-35A M-35B M-35C L-3A L-3B L-4A L-4B M-35D L-5A L-5B M-35E L-2A L-1A	800 1000 2600 1200 1300 1000 900 1600 3800 900 2200 2800 3500	94 203 387 60 78 97 103 648 252 268 984 146 402	9 18 30 5 6 10 10 Present canal with proper maintenance will be adequate Present canal with proper maintenance will be adequate Present canal with proper maintenance will be adequate Present canal with proper maintenance will be adequate Present canal with proper maintenance will be adequate	13 13 13 13 13 13 13	3 3 3 3 3 3 3	1184 1480 3848 1776 1924 1480 1332	1.1 1.4 3.6 1.7 1.8 1.4 1.2	60 60 60 60 60 60 60



ENGINEERING AND DESIGN DATA  
Area 8 - Poston - Salem - Vox - Johnsonville

CANAL No. (1)	LENGTH Ft. (2)	WATERSHED Ac. (3)	DISCHARGE c.f.s. (4)	CHANNEL DIMENSIONS		EXCAVATION Cu. Yds. (6)	RT. OF WAY CLEARING Ac. (7)	REQUIRED RT. OF WAY WIDTH Ft. (8)
				TOP WIDTH Ft. (5a)	BOTTOM WIDTH Ft. (5b)			
M-35F M-35G Total-35	900 2300 26,800	1422 1588	Present canal with proper maintenance will be adequate Present canal with proper maintenance will be adequate			13,024	12.2	
M-36A M-36B Total-36	1500 2700 4200	180 288	17 23	13 13	3 3	2220 3996 6216	2.1 3.7 5.8	60 60
M-37A M-37B Total-37	2300 2900 5200	184 264	17 22	13 13	3 3	3404 4292 7696	3.2 4.0 7.2	60 60
Area-8 Grand Total	277,000					271,813	252.5	









①

(Jains sheet 11)

1111

joins sheet 4)

JULY 1978 4-36631

A horizontal scale bar with vertical tick marks. The left end is labeled '0' and the right end is labeled '1 MILE'. There are four equal intervals between the two labels, indicated by three intermediate tick marks.

0 1 2 3 4 5 5000 FEET

APPROXIMATE SCALE: 1:50,000

0 2 KILOMETERS

This is one set of maps prepared by the Soil Conservation Service, U. S. Department of Agriculture, for a water runoff study for main drainageways and outlets in Florence County, South Carolina. The maps have been prepared in cooperation with Florence County Soil and Water Conservation District and under the financial sponsorship of Florence County. For information regarding the complete water runoff study report, write the Soil Conservation Service, U. S. Department of Agriculture, Columbia, South Carolina. This map was compiled as an uncontrolled mosaic from aerial photography flown in 1975. Surveys were executed in 1977 and maps prepared in 1978.



# WATER RUNOFF STUDY FOR MAIN DRAINAGEWAYS AND OUTLETS IN FLORENCE COUNTY, SOUTH CAROLINA



This is one set of maps prepared by the Soil Conservation Service, U. S. Department of Agriculture, for a water runoff study for main drainageways and outlets in Florence County, South Carolina. The maps have been prepared in cooperation with Florence County Soil and Water Conservation District and under the financial sponsorship of Florence County. For information regarding the complete water runoff study report, write the Soil Conservation Service, U. S. Department of Agriculture, Columbia, South Carolina. This map was compiled as an uncontrolled mosaic from aerial photography flown in 1975. Surveys were executed in 1977 and maps prepared in 1978.

For information regarding the complete water runoff study report, write the Soil Conservation Service, U. S. Department of Agriculture, Columbia, South Carolina. This map was compiled as an uncontrolled mosaic from aerial photography flown in 1975. Surveys were executed in 1977 and maps prepared in 1978.





WATER RUNOFF STUDY FOR MAIN DRAINAGEWAYS AND OUTLETS IN FLORENCE COUNTY, SOUTH CAROLINA



This is one set of maps prepared by the Soil Conservation Service, U. S. Department of Agriculture, for a water runoff study for main drainageways and outlets in Florence County, South Carolina. The maps have been prepared in cooperation with Florence County Soil and Water Conservation District and under the financial sponsorship of Florence County. For information regarding the complete water runoff study report, write the Soil Conservation Service, U. S. Department of Agriculture, Columbia, South Carolina. This map was compiled as an uncontrolled mosaic from aerial photography flown in 1975. Surveys were executed in 1977 and maps prepared in 1978.



WATER RUNOFF STUDY FOR MAIN DRAINAGEWAYS AND OUTLETS IN FLORENCE COUNTY, SOUTH CAROLINA  
(Join sheet 2)

⑤

(Joins sheet 2



This is one set of maps prepared by the Soil Conservation Service, U. S. Department of Agriculture, for a water runoff study for main drainageways and outlets in Florence County, South Carolina. The maps have been prepared in cooperation with Florence County Soil and Water Conservation District and under the financial sponsorship of Florence County. For information regarding the complete water runoff study report, write the Soil Conservation Service, U. S. Department of Agriculture, Columbia, South Carolina. This map was compiled as an uncontrolled mosaic from aerial photography flown in 1975. Surveys were executed in 1977 and maps prepared in 1978.

(P. 104g surior)

(Joins sheet 8)

APPROXIMATE SCALE: 1:50,000

0 1 MILE

0 5000 FEET

0 2000 METERS

0 1 2 KILOMETERS

JULY 1978 4.36631



WATER RUNOFF STUDY FOR MAIN DRAINAGEWAYS AND OUTLETS IN FLORENCE COUNTY, SOUTH CAROLINA



This is one set of maps prepared by the Soil Conservation Service, U. S. Department of Agriculture, for a water runoff study for main drainageways and outlets in Florence County, South Carolina. The maps have been prepared in cooperation with Florence County Soil and Water Conservation District and under the financial sponsorship of Florence County. For information regarding the complete water runoff study report, write the Soil Conservation Service, U. S. Department of Agriculture, Columbia, South Carolina. This map was compiled as an uncontrolled mosaic from aerial photography flown in 1975. Surveys were executed in 1977 and maps prepared in 1978.




⑦

(9 joins suit)



JULY 1978 4-36631






This is one set of maps prepared by the Soil Conservation Service, U. S. Department of Agriculture, for a water runoff study for main drainageways and outlets in Florence County, South Carolina. The maps have been prepared in cooperation with Florence County Soil and Water Conservation District and under the financial sponsorship of Florence County. For information regarding the complete water runoff study report, write the Soil Conservation Service, U. S. Department of Agriculture, Columbia, South Carolina. This map was compiled as an uncontrolled mosaic from aerial photography flown in 1975. Surveys were executed in 1977 and maps prepared in 1978.



# WATER RUNOFF STUDY FOR MAIN DRAINAGEWAYS AND OUTLETS IN FLORENCE COUNTY, SOUTH CAROLINA

This is one set of maps prepared by the Soil Conservation Service, U. S. Department of Agriculture, for a water runoff study for main drainageways and outlets in Florence County, South Carolina. The maps have been prepared in cooperation with Florence County Soil and Water Conservation District and under the financial sponsorship of Florence County. For information regarding the complete water runoff study report, write the Soil Conservation Service, U. S. Department of Agriculture, Columbia, South Carolina. This map was compiled as an uncontrolled mosaic from aerial photography flown in 1975. Surveys were executed in 1977 and maps prepared in 1978.



0 1 MILE

0 5000 FEET

APPROXIMATE SCALE: 1:50,000


0 2000 METERS

0 2 KILOMETERS



# WATER RUNOFF STUDY FOR MAIN DRAINAGEWAYS AND OUTLETS IN FLORENCE COUNTY, SOUTH CAROLINA

(Joins sheet 8)



0 1 MILE

0 5000 FEET

APPROXIMATE SCALE: 1:50,000

0 2000 METERS

0 2 KILOMETERS

JULY 1978 4-36631

This is one set of maps prepared by the Soil Conservation Service, U. S. Department of Agriculture, for a water runoff study for main drainageways and outlets in Florence County, South Carolina. The maps have been prepared in cooperation with Florence County Soil and Water Conservation District and under the financial sponsorship of Florence County. For information regarding the complete water runoff study report, write the Soil Conservation Service, U. S. Department of Agriculture, Columbia, South Carolina. This map was compiled as an uncontrolled mosaic from aerial photography flown in 1975. Surveys were executed in 1977 and maps prepared in 1978.

(Joins sheet 9)

(9 pages map)

(Joins sheet 11)



# WATER RUNOFF STUDY FOR MAIN DRAINAGEWAYS AND OUTLETS IN FLORENCE COUNTY, SOUTH CAROLINA

11

(Joins sheet 10)




This is one set of maps prepared by the Soil Conservation Service, U. S. Department of Agriculture, for a water runoff study for main drainageways and outlets in Florence County, South Carolina. The maps have been prepared in cooperation with Florence County Soil and Water Conservation District and under the financial sponsorship of Florence County. For information regarding the complete water runoff study report, write the Soil Conservation Service, U. S. Department of Agriculture, Columbia, South Carolina. This map was compiled as an uncontrolled mosaic from aerial photography flown in 1975. Surveys were executed in 1977 and maps prepared in 1978.



JULY 1978 4:36631



# WATER RUNOFF STUDY FOR MAIN DRAINAGEWAYS AND OUTLETS IN FLORENCE COUNTY, SOUTH CAROLINA



(Joins sheet 11)

(Joins sheet 6)

0 1 MILE

0 5000 FEET

APPROXIMATE SCALE: 1:50,000

0 2000 METERS

0 2 KILOMETERS

JULY 1978 4-36631

This is one set of maps prepared by the Soil Conservation Service, U. S. Department of Agriculture, for a water runoff study for main drainageways and outlets in Florence County, South Carolina. The maps have been prepared in cooperation with Florence County Soil and Water Conservation District and under the financial sponsorship of Florence County. For information regarding the complete water runoff study report, write the Soil Conservation Service, U. S. Department of Agriculture, Columbia, South Carolina. This map was compiled as an uncontrolled mosaic from aerial photography flown in 1975. Surveys were executed in 1977 and maps prepared in 1978.



